

12-215-147-20139-00-01

4-031858

D-14,266

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15- -

C SW SE SW /4 SEC. 02, 05 S, 20 W  
330 feet from S section line  
3630 feet from E section line

Operator license# 5352 Lease Wiltrout well # 1 SWD

Operator: Baird Oil Company, Inc. County Phillips 134.94

Address: P.O. Box 428 Well total depth 4152 feet  
Logan, Kansas 67646 Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 268 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cement Company License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: A.M. Day: 2 Month: December Year: 93

Plugging proposal received from: Jim Baird (Dennis Hamel KCC)

Company: Baird Oil Company, Inc. Phone: \_\_\_\_\_

Were: Order 200 sxs. 60/40 pozmix - 10% gel - 500# hulls.  
50 sxs. common cement.  
Perf. at 900' and 1570' - critical control shots.

Plugging Proposal Received by: Carl Goodrow  
Plugging operations attended by agent? All[  ], Part[  ], None[  ]

Completed: Hour: 11:30A.M., Day: 2, Month: December, Year: 93

Actual plugging report: 8 5/8" set @ 268' w/180 sxs. cwc. 4 1/2" set @  
3519' w/150 sxs. O.H. 4143' - 4152'. Squeezed 4 1/2" w/50 sxs. common,  
followed by 150 sxs. blend with 400# hulls mixed in to Max. P.S.I. 400#.  
Close in P.S.I. 200#. Squeezed 8 5/8" with 50 sxs. cement blend with  
100# hulls to Max. P.S.I. 500#. Close in P.S.I. 500#. Plug complete.

Remarks: \_\_\_\_\_  
Condition of casing(in hole): GOOD  BAD  Anhy.plug: YES  NO   
Bottom plug(in place): YES , CALC , NO  Dakota plug: YES , NO   
Plugged through TUBING , CASING . Elevation: \_\_\_\_\_ GL

I did  / did not  observe the plugging.

Carl Goodrow

(agent)

RECEIVED  
STATE CORPORATION COMMISSION

DEC 10 1993

Form CP-2/3 CONSERVATION DIVISION  
Wichita, Kansas

INVOICED

DEC 13 1993

DATE

INV. NO. 39499