

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-165-21684-00-00
Spot: S2NESE Sec/Twnshp/Rge: 36-19S-16W
1650 feet from S Section Line, 660 feet from E Section Line
Lease Name: WERHAHN Well #: 1
County: RUSH Total Vertical Depth: 3722 feet

Operator License No.: 5086
Op Name: PINTAIL PETROLEUM, LTD.
Address: 225 NORTH MARKET, STE 300
WICHITA, KS 67202

CIBP Size: feet: 3600 WITH 2 SX CMT
PROD Size: 5.5 feet: 3734 WITH 135 SX CMT
SURF Size: 8.625 feet: 636 WITH 325 SX CMT

\$120⁹⁷

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/10/2004 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: MIKE FRITZLER Company: PINTAIL PETROLEUM Phone: (316) 263-2243

Proposed Plugging Method: SAND TO 3630' & 5 SX CMT. PLUG AT 1000' WITH 15 SX GEL & 50 SX CMT. PLUG AT 660' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/10/2004 5:40 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

ANHYDRITE @ 993'. FLOWING CEDAR HILLS WATER. SET CIBP @ 3600' WITH 2 SX CMT ON TOP. SPOTTED PLUGS THROUGH CASING WHILE PULLING. 1ST PLUG AT 1000' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 660' WITH 75 SX CMT. PULLED CASING OUT OF HOLE. WELL STILL FLOWING. 3RD PLUG RAN TUBING TO 310'. PUMPED 150 SX COMMON CMT WITH 2% CC. PULLED TUBING & TOPPED OFF WITH 56 SX COMMON CMT WITH 2% CC.

Perfs:

Top	Bot	Thru	Comments
3708	3711		
3701	3705		
3686	3692		

RECEIVED
NOV 15 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 1880.5' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

RECEIVED
NOV 12 2004
KCC Dodge City

Signed

Richard W. Lacey
(TECHNICIAN)

INVOICED
DATE 11-15-04
INV. NO. 2005060816

Form CS-2/3