

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-25353-00-00
Spot: SWSESE Sec/Twnshp/Rge: 34-11S-19W
430 feet from S Section Line, 960 feet from E Section Line
Lease Name: ROSSIE MORGAN Well #: 1
County: ELLIS Total Vertical Depth: 3730 feet

Operator License No.: 32948
Op Name: TOMLINSON OPERATING, LLC
Address: PO BOX 9395
BEND, OR 97708

SURF Size: 8.625 feet: 328

#121²³

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 11/12/2004 7:00 AM
Plug Co. License No.: 6039 Plug Co. Name: L.D. DRILLING, INC.
Proposal Rcvd. from: BILL OWENS Company: L.D. DRILLING, INC. Phone: (620) 793-3051

Proposed Plugging Method: Order 215 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.
Two arbuckle tests - each recovered 10' of mud.

Plugging Proposal Received By: HERB DEINES Witness Type: NONE
Date/Time Plugging Completed: 11/12/2004 8:00 AM KCC Agent: HERB DEINES

Actual Plugging Report:

Perfs:

1st. Plug at 1500' w/25 sxs.
2nd. Plug at 850' w/100 sxs.
3rd. Plug at 380' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.

RECEIVED
NOV 16 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed _____

(TECHNICIAN)

INVOICED
DATE 11-16-04
INV. NO. 2005060822

NOV 12 2004