

4-070153

9-23

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-147-20,517-00-00

NE SE SW /4 SEC. 02, 05 S, 20 W
990 feet from S section line
2970 feet from E section line

Operator license# Expired
Operator: RLS

Lease: Wiltrout Well # 1
County: Phillips

Address: R.R. 2 - Box 11
Logan, Kansas 67646

Well total depth 3485 feet
Conductor Pipe: 0 inch @ 0 sxs.
Surface pipe 8 5/8 Inch @ 214 feet
W/150 sxs.

ABAND. oil well , Gas well , Input well , SWD. , D&A

Plugging contractor: Black Diamond Oil, Inc. License# 7076

Address: P.O. Box 641 - Hays, Kansas 67601

Company to plug at: Hour: 9:00 A.M. Day: 23 Month: September Year: 1999

Plugging proposal received from: Ken Vehige

Company: Black Diamond Oil Company Phone: 785-625-5891

Were: 5 1/2" casing set at 3484' w/400 sxs. Cement circulated.
PBTD 3171'. Perforations 3162' - 3165'.
Fluid level 3100'.
Ordered 340 sxs 60/40 pozmix - 10% gel with 500# hulls.

Plugging Proposal Received by: Rich Williams
Plugging operations attended by agent? All , Part , None

Completed: Hour: 10:30 A.M. Day: 23, Month: September, Year: 1999

Actual plugging report: Hooked up to backside and pressured to 500# cwc on long string.
Released pressure. Allied Cementing pumped 200 sxs 60/40 pozmix - 10% gel with 400# hulls.
Max. P.S.I. 1000#. S.I.P. 900#.

Remarks:
Condition of casing(in hole): GOOD BAD Anhy.plug: YES NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO
Plugged through TUBING , CASING . Elevation: 2025 GL

I did / did not observe the plugging.

Richard Williams
(agent)

INVOICED
DATE 9-30-99
INV. NO. 2000060628

RECEIVED
STATE CORPORATION COMMISSION
9-27-99 SEP 27 1999
CONSERVATION-DIVISION
Wichita, Kansas