

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-21566-00-00
Spot: NENE Sec/Twnshp/Rge: 10-14S-11W
660 feet from N Section Line, 660 feet from E Section Line
Lease Name: DOUBRAVA Well #: 2
County: RUSSELL Total Vertical Depth: 3080 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S. MARKET
WICHITA, KS 67202

PROD Size: 5.5 feet: 3000
SURF Size: 8.625 feet: 300

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/26/2003 9:00 AM
Plug Co. License No.: 3152 Plug Co. Name: POE SERVICING INC
Proposal Rcvd. from: DISTRICT #4 STAFF Company: KKC-HAYS, KANSAS Phone: (785) 625-0550

Proposed Drilling by Custom Oil Exploration in October of 1980.
Plugging Reported as gas well with no plugging report found.
Method:

Plugging Proposal Received By: HERB DEINES WitnessType: PARTIAL
Date/Time Plugging Completed: 08/26/2003 12:00 PM KCC Agent: HERB DEINES

Actual Plugging Report:

Ran tubing in hole and hit solid brige at 1200'.
Perforated at 1200' - 800' - 500'.
Hole dry. Mixed and pumped 130 sxs of cement with hulls.

Perfs:

RECEIVED
NOV 16 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed _____

(TECHNICIAN)

NOV 12 2004

replacement card

CUSTOM OIL EXPL
CHASE KS

10-14S-11W
~~C-E-2-NE~~
C-NE-NE

2 DOUBRAVA

site: 1/4 N & 3-1/2 E OF DORRANCE KS

cty: RUSSELL

API 15-167-21566

contr: CUSTOM TANK & LEASE

field: PLYMOUTH NW

geol: DAVE WILLIAMS

fr
date 10/30/80

spd
date 10/31/80

drig
comp 11/05/80

card
issued 10/29/81

last
revised 02/16/98

			*

ELV: 1760 EGL SMP

tops.....	depth/datum
ANH.....	760 + 1000
B/ANH.....	780 + 980
IND CV SD.....	2202 -442
TARK SD UPR.....	2260 -500
TARK SD LWR.....	2289 -529
HOW.....	2474 -714
HEEB.....	2865 -1105
DOUG SD.....	2918 -1158
LANS.....	3002 -1242
KC.....	3022 -1262
RTD.....	3080 -1320
NO LOG	

IP status

GAS, WAB, INTV NA , 04/01/81

INFO RELEASED: 2/16/98 - WAS SIGW - TEMP COMP

CSG: 8-5/8" 300 / 200 SX, 5-1/2" 3000 / 200 SX

NO CORES OR DSTS RPTD

MICT - CO, PF (TARK) INTV NA, AC'D, FRAC'D, SG, SI,

GAS WELL (POTENTIAL NOT RPTD), 4/1/81 - NO

OTHER INFO RELEASED BY OPERATOR OR ON KCC

RECORDS; ALL REQUESTS FOR INFO DENIED