

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-153-20554-00-00  
Spot: SEWNENESE Sec/Twnshp/Rge: 17-1S-34W  
2300 feet from S Section Line, 900 feet from E Section Line  
Lease Name: CAHOJ UNIT Well #: 938  
County: RAWLINS Total Vertical Depth: 4350 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N. WATER, STE 300  
WICHITA, KS 67202

PROD Size: 7 feet: 4349 w/525 sxs cmt  
SURF Size: 10.75 feet: 325 w/285 sxs cmt

# 141 38

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/05/2004 10:00 AM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: JOHN TURNER Company: MURFIN DRILLING CO., INC. Phone: (785) 443-1031

Proposed Plugging Method: Ordered 450 sxs Midcon II cement and 1500# hulls.  
Plug through tubing.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 11/05/2004 12:20 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

10.75 surface casing set at 325' w/285 sxs cement.  
7.0 production casing set at 4349' w/525 sxs cement.  
PBTB 4298'. Top of cement at 2137'.  
Ran tubing to 2512' - pumped 200 sxs cement with 900# hulls.  
Pulled tubing to 1200' - pumped 30 sxs cement with 300# hulls.  
Cement to surface - pulled tubing to surface.  
Connected to production casing - pumped 10 sxs cement.  
Max. P.S.I. 600#. S.I.P. 0#.  
Connected to surface casing - pumped 15 sxs cement.  
Max. P.S.I. 300#. S.I.P. 300#.

Perfs:

Top	Bot	Thru	Comments
4186	4189		
4141	4145		
4090	4096		
4063	4066		
4043	4048		
4000	4008		
3987	3989		

RECEIVED  
NOV 16 2004  
KCC WICHITA

Remarks: SWIFT SERVICES, INC.-TICKET #7328.

Plugged through: TBG

District: 04

Signed Darrel Dipman  
(TECHNICIAN)

INVOICED


DATE 11-16-04  
WV. NO. 20050608621

NOV 08 2004

GETTY OIL COMPANY  
 2705 VINE, UNIT #4 #938 CAHOJ UNIT 17-1-34W  
 HAYS, KS 67601 2300' FSI &  
 900' FEL, SE/4

CONTR MURFIN DRILLING CO. CTY RAWLINS

GEOL \_\_\_\_\_ FIELD CAHOJ



ELV 3113 KB SPD 7/7/84 CARD ISSUED 10/11/84 IP P 24 BO & 1664 BWPD  
 3108 GL LKC 3987-4189 OA

LOG	Tops	Depth/Datum	API 15-153-20,554
TOP	3795-	682	10 3/4 " 325/285SX, 7" 4349/525SX
OREAD	3887-	774	NO DST'S
DOUG	3946-	833	MICT - CO, PF (LKC) 4186-89, 4141-45, 4090-96, 4063-66,
LANS	3987-	874	4043-48, 4000-08, 3987-89, W/ 4 SPF, AC 7700G, SWB DWN,
MARM	4292-	1179	GSO, T&R, POP, P 24 BO & 1664 BWPD 8/25/84
PBTD	3993-	880	
RTD	4350-	1237	

COPYRIGHT 1984  
 INDEPENDENT OIL & GAS SERVICE, INC.  
 WICHITA, KANSAS