

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-153-05161-00-00
Spot: SENESE Sec/Twnshp/Rge: 18-1S-34W
1650 feet from S Section Line, 330 feet from E Section Line
Lease Name: CAHOJ B (48) Well #: 2
County: RAWLINS Total Vertical Depth: 4379 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N. WATER, STE 300
WICHITA, KS 67202

PROD Size: 5.5 feet: 4379 w/250 sxs cmt
SURF Size: 8.625 feet: 447 w/300 sxs cmt

#142 32

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/03/2004 1:00 PM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: JOHN TURNER Company: MURFIN DRILLING CO., INC. Phone: (785) 443-1031

Proposed Plugging Method: Ordered 350 sxs Midcon II cement and 1000# hulls.
Plug through tubing.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/03/2004 3:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 447' w/300 sxs cement.
5 1/2" production casing set at 4379' w/250 sxs cement.
PBTB 4346'. Top of cement at 2786'. Casing holes squeezed from 1245' to 1640' w/525 sxs cement.
Ran tubing to 2505' - pumped 125 sxs cement with 450# hulls.
Pulled tubing to 1200' - pumped 80 sxs cement with 400# hulls.
Cement to surface - pulled tubing to surface.
Connected to production casing - pumped 10 sxs cement.
Max. P.S.I. 300#. S.I.P. 0#.
Connected to surface casing - pumped 15 sxs cement.
Max. P.S.I. 300#. S.I.P. 300#.

Perfs:

Top	Bot	Thru	Comments
4072	4294		

RECEIVED
NOV 16 2004
KCC WICHITA

Remarks: SWIFT SERVICE, INC. - TICKET #7425.

Plugged through: TBG

District: 04

Signed Darrel Dipman
(TECHNICIAN)

INVOICED

DATE 11-16-04
CPL. NO. 2005060821

Form CP-2/3

NOV 08 2004

SKELLY OIL COMPANY

#2 CAHOJ 'B'

18-1-34W
SE NE SE

Contr. C. WENTWORTH

RAWLINS County

E 3163

Comm. 11-5-59


Comp. 12-25-59

IP 183 BOPD

Tops	Depth	Datum
TOP	3854	-691
LANS	4052	-889
B/KC	4318	-1155
MARM	4353	-1190
TD	4379	-1216

Casing

8" 450
 5" 4379
 PB 4346; PERF 18/4291-94; NS:
 ACID 250; NO NEW O: 36/4216-52
 1 BO/2 HR; ACID 500; SWB 38 BO,
 NW/6 HR; PLUG 4235; 35/4204-10
 12/4221-23; 5 BO & 13 B SW/5 HR
 ACID 250; SWB 22 BO & 14 1/2 BW
 7 1/2 HR; SQZ: 66/4153-64; SWB
 304 BO/4 HR, NW



CAHOJ POOL

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS