

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-22405-00-00
Spot: SWNWSW Sec/Twnshp/Rge: 9-14S-19W
1650 feet from S Section Line, 5055 feet from E Section Line
Lease Name: VONFELDT NORTH Well #: 3
County: ELLIS Total Vertical Depth: 3846 feet

Operator License No.: 33069
Op Name: ENCORE OPERATING COMPANY
Address: P. O. BOX 27710
DENVER, CO 80227

PROD Size: 4.5 feet: 3846 200 SX CMT
SURF Size: 8.625 feet: 201

\$125⁰⁰

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/11/2004 9:00 AM
Plug Co. License No.: 33346 Plug Co. Name: TR SERVICE AND RENTAL, INC.
Proposal Rcvd. from: ROLAND NYP Company: ENCORE OPERATING COMPANY Phone: (785) 737-3242

Proposed Plugging Method: 11-11-2004 - Ordered out 225 sxs 60/40 pozmix - 10% gel with 500# hulls.
11-12-2004 - Ordered out 250 sxs 60/40 pozmix - 10% gel with 1000# hulls.
Ran tubing with tapered mill. Cleaned out bridge 900' to 1000'.
Pulled mill. Ran back tubing to plug.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/12/2004 11:30 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perfs:

The following was not witnessed:
11-11-2004 - Ran tubing to 2000'.
Allied pumped 100 sxs 60/40 pozmix - 10% gel with 300# hulls. No circulation.
Pulled tubing to 1000'.
Allied pumped 125 sxs cement with 200# hulls. No circulation.
The following was witnessed:
11-12-2004 - Ran tubing to 1008' - tagged cement.
Allied pumped 120 sxs cement with 500# hulls. No circulation.
Pulled tubing to 600'.
Allied pumped 100 sxs cement with 500# hulls. Cement circulated.
PTOH. Topped off with 10 sxs cement - hole full.
Backside full of cement.

RECEIVED
NOV 17 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

MD

Signed Richard Williams
(TECHNICIAN)

INVOICE

DATE 11-17-04
NO. 2005060825

NOV 15 2004

replacement card

WEILERT ENTERPRISES
HAYS KS

#3

9-14S-19W
105'W. C SW NW SW

#2 VON FELDT

site: 4 S & 3/4 W OF YOCEMENTO KS
contr: HELBERG OIL CO

dy: ELLIS
field: KRAUS

API 15-051-22405

geol: _____
lr date 05/08/81 spd date 05/06/81 drig comp 05/11/81 card issued 01/07/82 last revised 07/05/99

ELV: 2215 EGL SMP
 tops.....depth/datum
 ANH.....1265 + 950
 ARB.....3810 -1595
 RTD.....3846 -1631

IP status:
 OIL, P 21 BO & 125 BWP, ARB 3812-3816, 10/30/81
 CORR & INFO REL: 7/5/99 - REDESCRIBED LOC; WAS
 OIL WELL - TEMP COMP
 CSG: 8-5/8" 201, 4-1/2" 3846
 COMMENT: REDESCRIBED LOC - IS ALSO 330'FSL &
 225'FWL, N/2 SW
 NO CORES OR DSTS RPTD
 MICT - CO, PF (ARB) 3812-3816, SWB DWN, GSO, NAT,
 POP, P 21 BO & 125 BWP, 10/30/81 - NO OTHER INFO
 RELEASED BY OPERATOR OR ON KCC RECORDS; ALL
 REQUESTS FOR INFO DENIED

COPYRIGHT 1999
 INDEPENDENT OIL & GAS SERVICE, INC.
 WICHITA, KANSAS