

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER ¹⁵⁻ 023-20437-00-00

LEASE NAME ZWEYGARDT

WELL NUMBER 1184

4604 Ft. from S Section Line

4743 Ft. from E Section Line

SEC. 4 TWP. 4S RGE. 41 (E) or (W)

COUNTY Cheyenne

Date Well Completed 05/25/02

Plugging Commenced 05/25/02

Plugging Completed 05/25/02

LEASE OPERATOR SAMEDAN OIL CORPORATION

ADDRESS 12600 Northborough, #250, Houston, TX 77067

PHONE# (281) 876-6105 OPERATORS LICENSE NO. 32987

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 05/25/02 (date)

by David Wann (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation Niobrara Depth to Top 1317 Bottom 1345 T.D. 1519

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Niobrara	Gas & Water	1317	1345	7"	256'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set.

Plugged well w/60:40 poz mix cement w/6% gel per District 4 office orders as follows:
40 sx cement @ 1310', 40 sx cement 1/2 in & 1/2 out of 7" surface casing (casing set @ 262' KB).
at 40' set a wiper plug w/10 sx cement from 40' to surface. Cut off casing 4' below surface.

Name of Plugging Contractor Excell Drilling Company License No. 28085

Address P.O. Box 305, Wray CO 80758-0305

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Samedan Oil Corporation

STATE OF Texas COUNTY OF Harris, ss.


Judy Throneberry, Regulatory Supervisor (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Judy Throneberry

(Address) 12600 Northborough, Houston, TX 77067

SUBSCRIBED AND SWORN TO before me this 3rd day of July, 19 2002

Patsy J. Nevill
Notary Public



Expires: 11-28-04

CR