

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Kahan & Associates, Inc.  
Address: P.O. Box 700780 Tulsa, OK 74170-0780  
Phone: (918) 492 - 9797 Operator License #: 4252  
Type of Well: Oil Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: 11/01/04 (Date)  
by: Mike Wilson (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (if needed attach another sheet)  
Misener Depth to Top: 3583' Bottom: 3589' T.D. \_\_\_\_\_  
Hunton Depth to Top: 3589' Bottom: \_\_\_\_\_ T.D. 3614'  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-155-02555-00-00  
Lease Name: Blake  
Well Number: 6  
Spot Location (QQQQ): NW - NE - SW -  
2310 Feet from  North /  South Section Line  
1650 Feet from  East /  West Section Line  
Sec. 23 Twp. 23 S. R. 4  East  West  
County: Reno  
Date Well Completed: 03/09/35  
Plugging Commenced: 11/02/04  
Plugging Completed: 11/03/04

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put in	Pulled Out
Chat	oil & water	3253'		16"	257'	None
Misener	"	3583'	3589'	13"	506'	"
Hunton	"	3589'	TD	7"	3585'	"
				5 1/2"	3465'	"

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Fill hole w/ sand above collapsed pipe @ 2605' to 2450'. Dump 5 sx cement.  
Perf 4 holes @ 350'. Spot 35 sx 60/40 poz @ 550'. Spot 120 sx poz @ 350'.  
Tie onto 5 1/2" and pump 80 sx w/ full cement returns on all annuli. Next day  
cement 5' down. Top off with cement.


Name of Plugging Contractor: Scott's Well Service, Inc. License #: 6819  
Address: P.O. Box 136, Roxbury KS 67476  
Name of Party Responsible for Plugging Fees: Kahan & Associates, Inc.  
State of Oklahoma County, Tulsa, ss.

RECEIVED  
NOV 12 2004  
KCC WICHITA

David M. Wilson Operations Manager (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) David M. Wilson  
(Address) P.O. Box 700780 Tulsa, OK 74170-0780

SUBSCRIBED and SWORN TO before me this 10<sup>th</sup> day of November, 2004  
Christine Hites My Commission Expires: 30 April 2008  
Notary Public #00006054



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

*BW*