

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-147-20,518-00-00

LEASE NAME Turnbull

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER #1

660' Ft. from S Section Line

990' Ft. from E Section Line

LEASE OPERATOR Western Kansas Exploration, Inc.

SEC. 36 TWP. 5 RGE. 19 (E) or (W)

ADDRESS 2700 Oak St., Hays, Kansas 67601

COUNTY Phillips

PHONE# (913) 628-2296 OPERATORS LICENSE NO. 3007

Date Well Completed 10-5-90

Character of Well D & A

Plugging Commenced 10-5-90

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 10-5-90

The plugging proposal was approved on October 1, 1990 (date)

by Bruce Bayse (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put In | Pulled out |
|-----------|--------------|------|------|-------|--------|------------|
| | Surface Pipe | 0 | 209' | 8 5/8 | 5 jts. | 0 |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Plugs: 3509 ARB. 20sks, 1520' 20sks, 920' 100sks, 260' 40sks, 40' 10sks wiper, 15sks rat hole 205sks, 60/40 poz, 6% gel, 2sks flow seal mixed throughout. Plug down @ 4:00 P.M. 10-5-90.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Western Kansas Drilling, Inc. License No. 4083

Address P.O. Box 126, Hays, Kansas 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Western Kansas Exploration, Inc.


STATE OF Kansas COUNTY OF Ellis, ss.

Stan Younger (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

Signature) [Signature]

(Address) P.O. Box 126, Hays, Kansas 67601

11-29-1990



AND SWORN TO before me this 28th day of November, 19 90

Nancy Taggart
Notary Public

My Commission Expires: 7-2-91

ORIGINAL

15-147-20518-00-00

DRILLER'S LOG

Operator: Western Kansas Exploration, Inc.

Contractor: Western Kansas Drilling, Inc.

Well & Well Description: Turnbull #1
C N/2-SE-SE 36-05-19 Phillips County, Kansas

Commenced: 9-27-90

Completed: 10-5-90

Character of Well: D & A

Elevation: 1972' GL 1977' KB


Casing: Ran 5 jts. of 8 5/8's set @ 209' cemented w/140sks
60/40 poz, 3% cc, 2% gel, plug down @ 6:00 p.m. 9-27-90.

Figures Indicate Bottom of Formations

| | |
|---------------|--------------|
| 0' - 1510' | Sand & Shale |
| 1510' - 1539' | Anhy. |
| 1539' - 1564' | Sand & Shale |
| 1564' - 2565' | Lime & Shale |
| 2565' - 3267' | Lime & Shale |
| 3267' - 3315' | Lime & Shale |
| 3315' - 3509' | Lime & Shale |
| 3509' - 3576' | Dolomite |

State of Kansas)
County of Ellis) ss:

I Stanley Younger, President of Western Kansas Drilling, Inc.
upon oath state that the above and foregoing is a true and correct copy of
the log of the Turnbull #1


Stanley Younger, President