

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Bldg.
 Wichita, Kansas 67202

Form CP-4
 Rev. 12-15-80

WELL PLUGGING RECORD

15-147-20355 00-00

Give All Information Completely
 Make Required Affidavit

COUNTY Phillips SEC. 35 TWP. 5S RGE. 19W E/W
 Location as in quarters or footage from lines:
C NE NW

	x		

Locate Well
 correctly on above
 Section Platt.

Lease Owner KRM Petroleum Corporation
 Lease Name Bender Well No. 1-35
 Office Address 820 Guaranty Bank Bldg. 817 Seventeenth St. Denver, CO
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole 80202
 Date Well Completed November 18, 1981
 Application for plugging filed Verbally, November 18, 1981
 Plugging commenced 6:00 p.m. November 18, 1981
 Plugging completed 11:00 p.m. November 18, 1981
 Reason for abandonment of well or producing formation _____

Dry Hole
 Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt
 Producing formation N/A Depth to top N/A bottom N/A T.D. N/A

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8" 20#	202'	None

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from _____ feet
 to _____ feet for each plug set.

Plugged with 140 sacks 50/50 Pozmix (4% gel, 3% CaCl)

Set 1st Plug @ 900' w/70 sacks
Set 2nd Plug @ 210' w/40 sacks
Set 3rd Plug @ 40' w/10 sacks
10 sacks rathole
10 sacks mousehole

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sun Oilwell Cementing, Inc.
P.O. Box 169, Great Bend, KS 67530

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

C.K. Morrison (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) C.K. Morrison
555 N. Woodlawn, Bldg. 1 - Suite 207
 (Address) Wichita, KS 67208

SUBSCRIBED AND SWORN TO before me this 31 day of December, 1981

Suzanne P. Graef
 Notary Public.

My Commission expires: 10/26/85



RECEIVED
 JAN 11 1982
 01-07-1982
 CONSERVATION DIVISION
 Wichita Kansas

November 23, 1981

CONTRACTOR'S WELL LOG

OPERATOR: KRM Petroleum Corporation
 CONTRACTOR: KANDRILCO, Ltd.
 WELL NAME: Bender #1-35
 LOCATION: C NE NW Section 35, T5S-R19W
 Phillips County, KS
 API NO.: 15-147-20,355
 COMMENCED: November 12, 1981
 COMPLETED: November 18, 1981

Drilled 222' of 12 1/4" hole. Set 202' of new 8 5/8" 24# casing at 202' with 165 sacks common - 3% CaCl, 2% Gel. Cement did circulate to surface. Plug was down at 9:30 p.m., November 12, 1981.

<u>FORMATION</u>	<u>TOP'</u>	<u>BOTTOM'</u>
Sand, Clay and Shale	0	222
Sand and Shale	222	1135
Sand	1135	1328
Red Bed	1328	1336
Shale and Lime	1336	1640
Shale and Lime	1640	2055
Shale and Lime	2055	2670
Lime and Shale	2670	3300
Lime and Shale	3300	3620

RTD 3620'. Plugged to abandon. Cemented with 140 sacks 50-50 pozmix, 4% gel, 3% CaCl. Set 70 sacks at 900', 40 sacks at 210', 10 sacks at 40', 10 sacks Rathole and 10 sacks Mousehole. Plugging was completed at 11:00 p.m., November 18, 1981.


STATE OF KANSAS, COUNTY OF SEDGWICK, SS:


I, C. K. Morrison, President, KANDRILCO, Ltd., do hereby state that the above is a true and correct copy of the Driller's Log for the KRM Petroleum Corporation Bender #1-35 well located in Phillips County, Kansas.

KANDRILCO, Ltd.


 C.K. Morrison - President

Subscribed and sworn to before me, a Notary Public, in and for the County and State aforesaid, as of this 23rd day of November, 1981.




 Suzanne P. Graef
 Notary Public

My Commission Expires: October 26, 1985