


15-147-00084-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Phillips County. Sec. 27 Twp. 5 Rge. (E) 19 (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE SE NE
Lease Owner Westgate-Greenland Oil Company
Lease Name Hilda Meyer Well No. 1
Office Address 1009 Central Building, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed May 27, 1951 19
Application for plugging filed May 27, 1951 (orally) 19
Application for plugging approved May 27, 1951 19
Plugging commenced May 28, 1951 19
Plugging completed May 28, 1951 19
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well
Producing formation Depth to top Bottom Total Depth of Well 3627 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Surface		0	323	8 5/8"	323	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.
Filled hole with heavy mud from 3627 to 225 feet
Set Land-Wells plug at 225 and ran 15 sacks cement
Filled hole with heavy mud from 185 feet to 35 feet
Set plug and ran 10 sacks cement to cellar base.

RECEIVED
STATE CORPORATION COMMISSION
JUN 1 1951
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)
Correspondence regarding this well should be addressed to Westgate-Greenland Oil Company
Address 1009 Central Building, Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
G. E. Bitler (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) G. E. Bitler
1009 Central Building, Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 31st day of May, 1951
Esther Russell
Notary Public.

My commission expires May 25, 1953.

PLUGGING
FILE SEC 27 T 5 R 19 W
BOOK PAGE 85 LINE 24

15-147-00084-00-00

COMPANY: Westgate Greenland Oil Co.
 CONTRACTOR: Jackson Drilling Corporation
 FARM: Meyer #1
 LOCATION: SE SE NE Section 27-5-19W
 Phillips County, Kansas
 ELEVATION: 2032
 COMMENCED: May 19, 1951
 COMPLETED: May 28, 1951

0	to	10	Clay
10	to	735	Shale
735	to	840	Sand & shale
840	to	920	Sand
920	to	1085	Shale & sand
1085	to	1120	Shale
1120	to	1325	Sand
1325	to	1610	Red bed & shale
1610	to	1645	Anhydrite
1645	to	1660	Shale
1660	to	1980	Shale & shells
1980	to	2140	Lime w/ shale breaks
2140	to	2175	Shale
2175	to	2230	Lime
2230	to	3160	Lime & shale
3160	to	3217	Lime
3217	to	3285	Lime w/ shale
3285	to	3460	Lime
3460	to	3551	Lime & shale
3551	to	3567	Conglomerate
3567	to	3585	Arb. Lime
3585	to	3627	Arbuckle
		3627	T.D.

8 5/8" casing set at 323 feet. Cemented with 200 sacks cement and 2 sacks calcium chloride.
 Drill stem test at 3307-33 feet. Opened 1 hour - recovered 60 feet slightly oil cut mud.
 Drill stem test at 3415-88 feet. Opened 1 hour - recovered 25 feet slightly oil cut mud.

Tops - Heebner 3228
 Toronto 3255
 Lansing 3272
 Arbuckle 3565

RECEIVED
 STATE CORPORATION COMMISSION
 JUN - 4 1951
 CONSERVATION DIVISION
 Wichita, Kansas

Dry and abandoned.

All measurements from top of derrick floor.

C E R T I F I C A T E

I, Clare A. Stewart, do hereby certify that the above and foregoing is a true and correct copy of log of the Meyer #1, Section 27-5-19W, Phillips County, Kansas, as reflected by files of the Jackson Drilling Corporation.

Clare A. Stewart
 Clare A. Stewart

Subscribed and sworn to before me, a Notary Public, within and for Johnson County, Kansas, this 1st day of June, 1951.

Naomi Mendus
 Naomi Mendus

My Commission expires May 3, 1954.

PLUGGING
 FILE SEC 27-5-19W
 BOOK PAGE 85 LINE 24