

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

15-147-00146-00-00

WELL PLUGGING RECORD

DPhillips County. Sec. 3 Twp. 5 S Rge. 19W (E) (W)

Location as "NE/CNW/SW" or footage from lines \_\_\_\_\_  
Lease Owner W. W. Sauvage  
Lease Name Reese Well No. 1  
Office Address Oberlin, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 6-17-56 19 56  
Application for plugging filed 6-18 19 56  
Application for plugging approved 6-18 19 56  
Plugging commenced 6-18 19 56  
Plugging completed 6-18 19 56  
Reason for abandonment of well or producing formation Dry Hole

NORTH


Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3625 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 115 feet to 110 feet for each plug set.

Filled hole with heavy mud thru drill pipe-pulled pipe to 115 feet  
Set 1st plug. Mixed 15sx cement 1/2 sx hulls. Filled hole with  
heavy mud to 40 feet set plug 10sx cement 1/2 sx hulls, filled  
hole to bottom of cellar

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sauvage & Dunn Drilling Co. Inc.  
Address Oberlin, Kansas

STATE OF Kansas, COUNTY OF Decatur, ss.  
W. W. Sauvage (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. W. Sauvage

(Address)

SUBSCRIBED AND SWORN TO before me this 22<sup>nd</sup> day of June, 1956

My commission expires May 17, 1959

Opal Sauvage  
Notary Public.

PLUGGING  
FILE SEC 3 T 5 R 19W  
BOOK PAGE 73 LINE 16

RECEIVED  
STATE CORPORATION COMMISSION

JUN 25 1956  
06-25-1956  
CONSERVATION DIVISION  
Wichita, Kansas

15-147-00146-00-00

OPERATOR: W. W. SAUVAGE  
LEASE OWNER: W. W. SAUVAGE  
FARM NAME: REESE  
CONTRACTOR: SAUVAGE & DUNN DRILLING CO. INC.

LOCATION: SE 1/4 NW 1/4 NW 1/4  
Sec. 3-5S-19W  
PHILLIPS COUNTY, KANSAS  
CASING RECORD: 150 ft. 8 5/8

DRILLER'S LOG

Figures denote bottom of formations

cellar	5
sand & shale	670
shale & sand	940
shale-sand-pyrite	1020
lime	1140
red bed & shale	1562
shale	1580
red bed & shale	1795
shale & lime	2040
shale & lime	2180
lime & shale	2260
lime & shale	2400
shale & lime	2526
lime & shale	2655
lime & shale	2681
lime & shale	2755
lime & shale	2860
lime & shale	2935
lime & shale	3038
lime & shale	3150
shale & lime	3244
lime	3303
lime	3325
lime & shale	3405
lime	3463
lime & shale	3510
lime & shale	3576
Total rotary depth	3625

CERTIFICATE

STATE OF KANSAS)  
DECATUR COUNTY ) ss

I hereby certify that the foregoing is, to the best of my knowledge and belief a full, true and correct drilling log as shown by the daily drilling reports in connection with afore-said well.

*W. W. Sauvage*  
For Sauvage & Dunn Drilling Co., Inc.

Subscribed and sworn to before me, the undersigned, a Notary Public, this 29<sup>th</sup> day of June, 1956

*W. W. Sauvage*  
Notary Public

My commission expires May 17, 1959

PLUGGING  
FILE SEC 3 T 5 R 19W  
BOOK PAGE 73 LINE 16

RECEIVED  
STATE OF KANSAS  
06-25-1956  
JUN 25 1956  
CONSERVATION SERVICE  
PHILLIPS COUNTY, KANSAS