

STATE OF KANSAS  
STATE CORPORATION  
COMMISSION  
130 South Market Room 2078  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R. 82-3-117

API NUMBER 15-033-21,103 -00 -00

LEASE NAME Thompson

TYPE OR PRINT

NOTICE: Fill out completely  
and return to Cons. Div.  
office within 60 days.

WELL NUMBER 1-13

~~3734~~  
~~1512~~ Ft. from N S Section Line

~~4714~~  
~~692~~ Ft. from E W Section Line

u/w/lo  
KCC  
BEM  
GPS  
Coordin.

LEASE OPERATOR American Warrior, Inc.

SEC. 13 TWP. 32S RGE. 18 (E) or (W)

ADDRESS P.O. Box 399, Garden City, KS 67846

COUNTY Comance

PHONE # 620-275-2963 OPERATOR'S LICENSE NO. 4058

Date Well Completed 6/16/2000

Character of Well Good

Plugging Commenced 10/25/2004

(Oil, Gas, D&A, SWD, Input, Water Supply Well)  
The plugging proposal was approved on 10/26/2004

Plugging Completed 10/29/2004

by Mike Maier (KCC District Agent's Name).

is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top 4934 Bottom 4953 T. D. 5461.5800

Show depth and thickness of all water, oil and gas formations.

OIL, GAS, OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size  | Put in | Pulled out |
|-----------|---------|------|----|-------|--------|------------|
|           |         |      |    | 8 5/8 | 641    | None       |
|           |         |      |    | 5 1/2 | 5161   | 3150       |
|           |         |      |    |       |        |            |
|           |         |      |    |       |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set.

10/25 - pull 103.....10/26 - lay down rods and tubing, set CIBP at 4850, spot 2 sacks portland cement with dump bailer  
10/27 - stretch and cut pipe at 5150.....10/28 - lay down 5 1/2.....10/29 - run 2 3/8 tubing to 1100, load with 12 sacks gel  
200 hulls, spot 50 sacks cement, pull to 650', spot 50 sacks, pull to 40', load surface with 10 sacks 60/40 POZ, 6 % gel

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Clarke Corporation License No. 5105


Address P.O. Box 187, 107 W. Fowler, Medicine Lodge, KS 67104

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: American Warrior, Inc.

STATE OF Kansas COUNTY OF Barber, ss.

John Swinford (Employee of Operator) or (Operator) of above described well, being

first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filled that the same are true and correct, so help me God.



(Signature) John Swinford

(Address) P.O. Box 187, Medicine Lodge, KS 67104

SUBSCRIBED AND SWORN TO before me this 12 day of November 2004

Glenda Morrison  
Notary Public

My Commission Expires: November 30, 2006

RECEIVED  
NOV 15 2004  
KCC WICHITA

*ben*