

RECEIVED

OCT 20 2004

KCC WICHITA

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

WELL PLUGGING APPLICATION

Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15-097-20108-00-01 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date 02/13/73

Well Operator: Lee Banks d/b/a Banks Oil Company KCC License #: 5152
(Owner / Company Name) (Operator's)

Address: 7701 E. Kellogg, Suite 885 City: Wichita

State: Kansas Zip Code: 67207 Contact Phone: (316) 612-1186

Lease: Smith #1 Well #: 1 Sec. 32 Twp. 30 S. R. 18 East West

NW/4 - SW/4 Spot Location / QQQQ County: Kiowa

1980 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

660 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8 5/8 Set at: 540' Cemented with: 150 Sacks

Production Casing Size: 4 1/2 Set at: 5185' Cemented with: 150 Sacks

List (ALL) Perforations and Bridgeplug Sets: 5055' - 61' Bridgeplug 4602

Elevation: 2183 (G.L. / B.) TD.: 5190 PBDT: 4602 Anhydrite Depth: 1010'
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Attempt to make pump change, found hole or bad csg @ approx. 2325' - set BP @ 4602' - packer @ 2137' Squeeze with 150 sacks. Pressure up held - attempt to drill out-iron- csg shifted on squeeze - Plugging, pull minimum of 1010' 4/12 csg spot plug @ 1010'-40 sacks cement 560'-50 sacks 40'-10 sacks 15 sacks gel on side.
Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? _____

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Lee Banks or Brain Siroky

Phone: (316) 612-1186 / 316-672-5713

Address: 7701 E. Kellogg, Suite 885 City / State: KCC 11-9-04, SKA, Per Operator

Plugging Contractor: Siroky Oil Management Genesis Well Service KCC License #: 33093
(Company Name) (Contractor's)

Address: P.O. Box 464 - Pratt, Kansas Phone: (316) 672-5713 5625

Proposed Date and Hour of Plugging (if known?): When Rig is available.

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 10-18-04 Authorized Operator / Agent: [Signature]
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202



KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor Brian J. Moline, Chair Robert E. Krehbiel, Commissioner Michael C. Moffet, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Banks, Lee DBA Banks Oil Co
Suite 885
7701 E. Kellogg
Wichita, KS 67207

October 27, 2004

Re: SMITH #1
API 15-097-20108-00-01
NWSW 32-30S-18W, 1980 FSL 660 FWL
KIOWA COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.


Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(620) 225-8888

Sincerely



David P. Williams
Production Supervisor