

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-083-21042-00-02
Spot: E2SESENW Sec/Twnshp/Rge: 14-23S-22W
2970 feet from S Section Line, 2970 feet from E Section Line
Lease Name: OSBORNE OWWO Well #: 2
County: HODGEMAN Total Vertical Depth: 4465 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

PROD Size: 5.5 feet: 4450 WITH 225 SX CMT
SURF Size: 8.625 feet: 1322 WITH 525 SX CMT

\$145¹¹

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/05/2004 10:40 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: KEN Company: AMERICAN WARRIOR Phone: (620) 275-7461

Proposed Plugging Method: SAND TO 4300' WITH 5 SX CMT. PLUG A T1350' WITH 20 SX GEL & 60 SX CMT. PLUG AT 500' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE MIDDLETON WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/05/2004 12:30 PM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:

PBTD 4435'. SAND TO 4300' WITH 5 SX CMT. 1ST PLUG PULL CASING TO 1350' & SPOT 20 SX GEL & 60 SX CMT. 2ND PLUG PULL TO 500' & SPOT 40 SX CMT. 3RD PLUG PULL TO 40' & SPOT 15 SX CMT. STAYED FULL.

Perfs:


Top	Bot	Thru	Comments
4389	4392		

RECEIVED
NOV 12 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2000' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed _____

[Signature]
(TECHNICIAN)

INVOICED

DATE 11-12-04
BY 2005060799

Form CP-23 *[Signature]*