

7-13

201 R

4-031723

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-147-20,188 -00-00
SESE NW
NW SE NW /4 SEC. 24, 05S, 18 W
2070 3630 feet from S section line
2070 3630 feet from E section line

Operator license# 5146 Lease McKinley well # 3

Operator: Rains & Williamson Oil Co. County Phillips 110.17

Address: 220 W. Douglas Well total depth 3390 feet
#435 Page Center Conductor Pipe: 0 inch @ 0 feet
Wichita, Kansas 67202 Surface pipe 8 5/8 Inch @ 202 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Kelso License# 6050

Address: Chase, Kansas

Company to plug at: Hour: P.M. Day: 13 Month: July Year: 92

Plugging proposal received from: Monte

Company: Kelso Phone:

Were: Order 225 sx. 65/35 pozmix - 10% gel. - 500# hulls.
Allied Cement Company.

Plugging Proposal Received by: Carl Goodrow
Plugging operations attended by agent? All [], Part [X], None []

Completed: Hour: 6:30P.M., Day: 13, Month: July, Year: 92

Actual plugging report: 8 5/8" set @ 202' w/150 sx. 4 1/2" set @ 3376'
w/150 sx. P.B.T.D. 3336'. Shots @ 1900' - 860'. Recovered 860' of
4 1/2" casing. Mix and pump bottom plug 75 sx. cement blend with hulls
Lay down pipe. Squeeze 8 5/8" with total 225 sx. cement blend w/500#
hulls mixed in to Max. P.S.I. 700#. Close in P.S.I. 300#
Plug complete.

Remarks:
Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO
Bottom plug(in place): YES X, CALC, NO Dakota plug: YES X, NO
Plugged through TUBING, CASING X. Elevation: GL
I did [X], did not [] observe the plugging. Carl Goodrow

INVOICED
DATE 8-4-92
INV. NO. 35856

RECEIVED
STATE CORPORATION COMMISSION
JUL 29 1992
CONSERVATION DIVISION
Wichita, Kansas
(agent)
Form CP-2/3