

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-24311-00-00
Spot: W2SENE Sec/Twnshp/Rge: 20-19S-23W
1980 feet from N Section Line, 990 feet from E Section Line
Lease Name: MINER Well #: 1
County: NESS Total Vertical Depth: 4435 feet

Operator License No.: 6569
Op Name: SCHMITT, CARMEN, INC.
Address: PO BOX 47
GREAT BEND, KS 67530

SURF Size: 8.625 feet: 217

\$ 144¹⁴

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 11/05/2004 7:30 PM
Plug Co. License No.: 5184 Plug Co. Name: SHIELDS OIL PRODUCERS INC
Proposal Rcvd. from: BURT BEERY Company: SHIELDS OIL PRODUCERS INC Phone: (785) 483-3141

Proposed Plugging Method: 1ST PLUG AT 1600' WITH 50 SX CMT. 2ND PLUG AT 850' WITH 80 SX CMT. 3RD PLUG AT 400' WITH 40 SX CMT. 4TH PLUG AT 220' WITH 40 SX CMT. 5TH PLUG AT 40' WITH 10 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: NONE
Date/Time Plugging Completed: 11/05/2004 10:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

Perfs:


1ST PLUG AT 1600' WITH 50 SX CMT. 2ND PLUG AT 850' WITH 80 SX CMT. 3RD PLUG AT 400' WITH 40 SX CMT. 4TH PLUG AT 220' WITH 40 SX CMT. 5TH PLUG AT 40' WITH 10 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

RECEIVED
NOV 12 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01



Signed

Michael Maier
(TECHNICIAN)

INVOICED
DATE 11-12-04
INV NO. 2005060801

Form CP-2/3