

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-097-21265-00-00
Spot: NWNW Sec/Twnshp/Rge: 10-27S-19W
4620 feet from S Section Line, 4620 feet from E Section Line
Lease Name: BARRETT Well #: 1
County: KIOWA Total Vertical Depth: 5000 feet

Operator License No.: 5118
Op Name: TGT PETROLEUM CORPORATION
Address: 7570 W 21ST ST N, STE1010D PO BOX
WICHITA, KS 67275

PROD Size: 5.5 feet: 4635 WITH 240 SX CMT
SURF Size: 8.625 feet: 410 WITH 250 SX CMT

50
\$162

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/22/2004 3:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JERRY SULLIVAN Company: TGT PETROLEUM Phone: (316) 773-2266

Proposed Plugging Method: SAND TO 4500' & 5 SX CMT. PLUG AT 1250' WITH 12 SX GEL & 50 SX CMT. PLUG AT 440' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/22/2004 5:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SAND BACK TO 4500' & PUT 5 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. SPOT PLUGS THROUGH 5 1/2" CASING. 1ST PLUG AT 1250' WITH 12 SX GEL & 50 SX CMT. 2ND PLUG AT 440' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:


Top	Bot	Thru	Comments
4565	4569		

RECEIVED
NOV 12 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ACID SERVICES. RECOVERED 2437' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Stephen J. Pfeifer
(TECHNICIAN)

INVOICED

DATE

11-12-04

INV NO

2005060802

Form SP-2/4