

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-147-20,444 - 00-00

NE NE SW, Sec. 36, T 5 S, R 18 W

2310 feet from N/S section line

2310 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6029

Lease Name Jackson Well # 1

Operator: Ladd Petroleum
Name & Box 520
Address Great Bend, Ks. 67530

County Phillips

Well Total Depth 3557 feet 115.60

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 261-150 sks

Abandoned Oil Well Gas Well Input Well SWD Well D&A XX

Other well as hereinafter indicated

Plugging Contractor Red Tiger Drilling Company License Number 5302 Rig Tag 75

Address 1720 Kansas State Bank Bldg. Wichita, Ks. 67202

Company to plug at: Hour: 11:15 AM Day: 23 Month: May Year: 1984

VERBAL PLUGGING ORDERS GIVEN TO Sam Wagner

(company name) Red Tiger Drilling Company (phone)

were: Order 210 lbs. 50/50 pozmix 6% gel 3% cal. cl. 1 sk lfo-cel and 8 5/8" plug.

Spot with drill pipe with no less than 36 vis. mud between all plugs, with good circulation and no fluid loss.

Signed Gilbert P. Leiker (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:15 AM Day: 23 Month: May Year: 19 84

ACTUAL PLUGGING REPORT

1st plug @ 3550 w/25 sks

2nd plug @ 1470 w/25 sks

3rd plug @ 800 w/100 sks 1 sk cel-flake

4th plug @ 280 w/40 sks

5th plug @ 40 w/8 5/8" plug 1/2 sk hulls 10 sks cmt

10 sks in Rat Hole

Remarks: Cemented by Allied

Partially witnessed by Dale Balthazor.

RECEIVED STATE CORPORATION COMMISSION

MAY 29 1984

CONSERVATION DIVISION Wichita, Kansas

5-29-84

I hereby certify that the above plugging instructions were given as herein stated and that (did) did not observe this plugging.

INVOICED

DATE 5-31-84

INV. NO. 1758

5-23 JUN 08 1984

Signed Gilbert P. Leiker (TECHNICIAN)

FORM CP-2/3 Rev. 9-82