

15-147-20412-00-00

6 030878

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 6-22-83
1050 FWL
630 FNL NW NWSEC. 11, T 5 S, R 20 W/X

TECHNICIAN'S PLUGGING REPORT

Operator License # 5352

4650 feet from S section line
4230 feet from E section line

Operator: Baird Oil Co. Inc.
Name & Address: Box 428

Lease Name Mitchell Well # 2
County Phillips 113.13

Logan, Kansas 67646

Well Total Depth 3481' feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 205

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Chase, Ks.

Company to plug at: Hour: PM Day: 18 Month: 5 Year: 19 87

Plugging proposal received from Millard Kelso

(company name) Kelso Casing (phone)

were: 8 5/8" set at 205 cwc 4 1/2" set at 3472' with 240 sx PBD 3410'
Perf's 3169-3370 order com. sand. and cmt. shoot and strip pipe - order 150 sx

ATL 65/35 pox 10% gel 2% dicel 5 sx hulls

Allied Cmt. Co.

Plugging Proposal Received by Dale Balthazor and Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 2:PM Day: 18 Month: 5 Year: 19 87

ACTUAL PLUGGING REPORT Sand bottom to 3100' with 4 sx com. cmt. on sand w/bailer.

5 shots at 2397' - 1803' - 1613' - 1312' - 1245' recovered 1245' of csg.

Mix and pump down 8 5/8" csg. 5 sx hulls with 150 sx ATL cmt blend

Max. PSI 600 # close in at 200 # Plug Complete.

RECEIVED
STATE CORPORATION COMMISSION
7-16-87
JUL 16 1987

Remarks: Plug checked by Dale B. OK
(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
Wichita, Kansas

INVOICED
I did not observe this plugging.

DATE 7-16-87

Signed Carl Goodrow
(TECHNICIAN)
Carl Goodrow

INV. NO. 17498