

6-090453

3-1

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-147-20,530 <sup>00-00</sup>  
SW SW NE /4 SEC. 15, 05 S, 18 W  
2970 feet from S section line  
2310 feet from E section line

*Rec'd  
3-15-91*

Operator license# 5140 Lease Shaw well # 1

Operator: Frontier Oil Company County Phillips

Address: 125 North Market, Suite 1720 Well total depth 3430 <sup>111.47</sup> feet  
Wichita, Kansas 67202 Conductor Pipe:        inch @        feet  
Surface pipe 8 5/8 Inch @ 221 feet

Aband. oil well       , Gas well       , Input well       , SWD       , D & A X

Plugging contractor: Red Tiger Drilling Company License# 5302

Address: Wichita, Kansas

Company to plug at: Hour: PM Day: 26 Month: February Year: 1991

Plugging proposal received from: Bill Ayres

Company: Red Tiger Drilling Company phone:                     

Were: Spot plugs through drill pipe w/ heavy mud between all plugs.

1st plug @ 1600 feet with 20 sacks Rat hole: 15 sacks

2nd plug @ 925 feet " 100 " Mousehole:        sacks

3rd plug @ 270 feet " 40 "

4th plug @ 40 feet " wiper plug & 10 sacks

5th plug @        feet

Plugging Proposal Received by: Ed Schumacher P.I.R.T. III

Plugging operations attended by agent? All[    ], Part[    ], None[ X ]

Completed: Hour: 7:30 AM, Day: 1, Month: March, Year: 1991

Actual plugging report: Hole reported plugged as above.  
Order 185sx 60/40 pozmix w/ 6% gel and 2sx celloflake or flowcel.

Remarks: Elevation: 2023 GL, Anhydrite depth: 1584 - 1610 feet

Did Not penetrate Arbuckle, cemented by Allied Cementing Company

I did[    ] / did not[ X ] observe the plugging. Ed Schumacher

**INVOICED**

DATE 3-15-91

INV. NO. 31173

*Gibbs*

Ed Schumacher P.I.R.T. III  
(agent)

3-1