

6010234

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 147-20,459-00-00
SE NE NW
NW, SEC. 3, T 5 S, R 18 W/E
4150 feet from ~~NXS~~ SE section line
2970 feet from ~~WXS~~ SE section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6771

Lease Name Armstrong Well # 3

Operator: Ozark Enterprises
Name & Address: Box 427
Logan, Ks.

County Phillips
Well Total Depth 3330 108.23 feet
Conductor Pipe: Size 0 feet
Surface Casing: Size 8 5/8 feet 200

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A XX

Other well as hereinafter indicated _____

Plugging Contractor R&C Drilling Company License Number 9087

Address Box 296, Hays, Ks. 67601

Company to plug at: Hour: PM Day: 3 Month: October Year: 1984

Plugging proposal received from Rick Finnesy

(company name) R&C Drilling Company (phone) _____

were: Order 185 sks cmt 50/50 pozmix 6% gel 3% cal. cl., 1 sk flo seal, 1 sk hulls and
8 5/8" plug. Spot with drill pipe with no less than 36 vis. mud between all plugs,
with good circulation and no fluid loss.

Plugging Proposal Received by A. F. B.
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None XX

Operations Completed: Hour: 10 PM Day: 3 Month: October Year: 19 84

ACTUAL PLUGGING REPORT

- 25 sks @ 1350
- 100 sks @ 790 w/1 sk flo-seal
- 40 sks @ 230
- 10 sks @ 40 on Solid Bridge
- 10 sks in Rat Hole

Remarks: Cemented by Allied
(If additional description is necessary, use BACK of this form.)

RECEIVED
STATE CORPORATION COMMISSION
OCT 09 1984
10-9-84
CONSERVATION DIVISION
Wichita, Kansas

Signed Dale F. Battazzo
(TECHNICIAN) 10-5-84 27

INVOICED
DATE 10-15-84
INV. NO. 4280