

4-070154

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-147- 20,472-00-00
W2NE1/4
~~C N2 NW~~ /4 SEC. 02, 05 S, 18 W
4650 feet from S section line
~~4000~~ 3940 feet from E section line

10-26

106.08

Operator license# 31838

Lease: Armstrong Well # 5

Operator: Phase II Oil

County: Phillips

Address: P.O. Box 254
Logan, Kansas 67646

Well total depth 3264 feet
Conductor Pipe: 0 inch @ 0 sxs.
Surface pipe 8 5/8 Inch @ 212 feet
W/140 sxs.

ABAND. oil well , Gas well , Input well , SWD. , D&A

Plugging contractor: Phase II Oil License# 31838

Address: P.O. Box 254 - Logan, Kansa 67646

Company to plug at: Hour: 8:00 A.M. Day: 26 Month: October Year: 1999

Plugging proposal received from: O.C. Cooper

Company: Phase II Oil Phone: 785-421-2918

Were: 4 1/2" casing set at 3264' w/475 sxs.
Fluid Level 150' from surface. Perforations 3146' - 3230'.

Plugging Proposal Received by: Rich Williams
Plugging operations attended by agent? All , Part , None

Completed: Hour: 11:00 A.M. Day: 26, Month: October, Year: 1999

Actual plugging report: Ran 2" tubing to 1500'. Well flowing. Dakota sand and water.
Swift Services pumped 100 sxs with 200# hulls - cement circulated. PTOH and squeezed 10 sxs
at Max. P.S.I. 450#. S.I.P. 250#. Checked backside - pressured up to 600#.

Remarks:
Condition of casing(in hole): GOOD BAD Anhy.plug: YES NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO
Plugged through TUBING , CASING . Elevation: 1826 GL

I did / did not observe the plugging.

Richard Williams
(agent)

INVOICED
DATE 11-5
INV. NO. 60800

RECEIVED Form CP-2/3
STATE CORPORATION COMMISSION
NOV - 1 1999
11-99
CONSERVATION DIVISION
Wichita, Kansas

P