

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-139-20094-00-00
Spot: NWNWSW Sec/Twnshp/Rge: 2-17S-14E
2098 feet from S Section Line, 581 feet from W Section Line
Lease Name: WILLIAMS Well #: 13-2
County: OSAGE Total Vertical Depth: 1948 feet

Operator License No.: 32886
Op Name: BURLINGTON RESOURCES OIL & GAS
Address: 717 TEXAS ST. #2100
HOUSTON, TX 77002

CIBP Size: feet: 1510
CIBP Size: feet: 1550
CIBP Size: feet: 1745
CIBP Size: feet: 1773
PROD Size: 5.5 feet: 1948
SURF Size: 8.625 feet: 174 87 SX

#6331

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/03/2004 8:00 AM
Plug Co. License No.: 32006 Plug Co. Name: HURRICANE WELL SERVICE, INC.
Proposal Rcvd. from: KYLE HUDSON Company: _____ Phone: (432) 688-6972

Proposed Plugging Method: PER INSTRUCTIONS FROM KCC DIST 03 OFFICE

Plugging Proposal Received By: MICHAEL HEFFERN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/04/2004 5:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:
ran tubing to 1492', pumped 35 bbl of mud, mixed & pumped 25 sxs cement, pulled tubing out, shot casing @ 993', pumped 20 bbl of mud, pulled 2 joints of casing to 907' pumped 25 sxs cement, pulled casing out, ran 7 joints of tubing to 218' pumped 75 sxs cement to surface, pulled tubing out.

RECEIVED
KCC DISTRICT #3
NOV 15 2004
MH
CHANUTE, KS

Perfs:

Top	Bot	Thru	Comments
1785	1760		SPF
1780	1782		SPF
1736	1737		SPF
1516	1517		SPF
1501	1502		SPF

RECEIVED
NOV 19 2004
KCC WICHITA

Remarks:
Plugged through: TBG

District: 03 Signed: Michael Heffern (TECHNICIAN)

INVOICED
DATE 11.22.04
INV. NO. 2005060834