

6 041226

9-13-90 15-147-19118-00-03 NOC

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- E - 17,919

SW SW, SEC. 14, T 5 S, R 20 W/E

330 feet from S section line

4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Lease Name Templeton Well # 3 W

Operator: Oxy U.S.A. Inc.

County Phillips 120.15

Name & Address Box 38

Well Total Depth 3697 feet

Hill City, Ks. 67642

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 175 w/125 sks

Abandoned Oil Well Gas Well Input Well xx SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor B. J. Titan License Number

Address Hays, Ks.

Company to plug at: Hour: 10:00AM Day: 13 Month: Sept Year: 19 90

Plugging proposal received from Jim Norvell

(company name) Oxy USA (phone)

were: 5 1/2 casing set at 3526 w/150 sks cement: perfs at 3224. Perf anhy at 1590;

Perf base dakota 1140; Ordered 50 sks common cement. Ordered 350 sks

65/35 poz 6% gel w/1/4 lb. f.c. plus 600 lbs hulls.

Plugging Proposal Received by Dale Balthazor

(TECHNICIAN)
Dennis L. Hamel

Plugging Operations attended by Agent?: All xx Part None

Operations Completed: Hour: 12:30PM Day: 13 Month: Sept Year: 19 90

ACTUAL PLUGGING REPORT Pumped in 5 1/2 casing w/50 sks common cement w/1/4 lb f.c. plus

pumped in add 275 sks cement w/1/4 f.c. and 500 lbs. hulls mixed in cement. Max 400 lbs.

S.I. 250 lbs. Pumped in 8 5/8 casing w/75 sks cement w/1/4 lb. f.c. and 150 sks hulls mixed

in cement. Max 400 lbs. S.I. 200 lbs.

RECEIVED
STATE CORPORATION COMMISSION

OCT 8 1990
10-08-90

CONSERVATION DIVISION
Wichita, Kansas

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 10-10-90

INV. NO. 29617

Signed Dennis L. Hamel (TECHNICIAN)

Dennis L. Hamel