

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-113-20404-00-00  
Spot: W2NWNW Sec/Twnshp/Rge: 24-19S-1W  
4620 feet from S Section Line, 4950 feet from E Section Line  
Lease Name: LEFFLER Well #: 1  
County: MCPHERSON Total Vertical Depth: 2981 feet

Operator License No.: 5399  
Op Name: AMERICAN ENERGIES CORPORATION  
Address: 155 N. MARKET, STE 710  
WICHITA, KS 67202

PROD Size: 5.5 feet: 2975 75 SX CMT  
SURF Size: 8.625 feet: 140 100 SX CMT

*\$96<sup>88</sup>*

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/11/2004 12:00 PM  
Plug Co. License No.: 5399 Plug Co. Name: AMERICAN ENERGIES CORPORATION  
Proposal Rcvd. from: ALAN L DEGOOD Company: AMERICAN ENERGIES CORPORAT Phone: (316) 263-5785

Proposed Plugging Method: SET 50' SD PLUG OVER PERF, CAP WITH 5 SX CMT, FILL HOLE WITH MUD TO 250', CMT TO SURFACE WITH 125 SX. NO SALT SECTION IN T19S-R1W.

Plugging Proposal Received By: JEFF KLOCK WitnessType: NONE  
Date/Time Plugging Completed: 11/11/2004 4:00 PM KCC Agent: MICHAEL WILSON

Actual Plugging Report:

Sanded to 2,850' & topped with 5 sxs. cement. Shot casing off at 2,052' & pulled same. Pushed rubber plug to 425' & filled with rock to 400'. Ran tubing to 400' & spotted 35 sxs. cement. Pulled tubing to 245' & circulated 170 sxs. cement to the surface.

Perfs:

Top	Bot	Thru	Comments
2922	2934		

RECEIVED  
NOV 19 2004  
KCC WICHITA

RECEIVED  
KCC DISTRICT #2  
NOV 16 2004  
WICHITA, KS

Remarks: USE 60/40 POSMIX W/4% GEL BY COPELAND ACID & CEMENT. INVOICE # 25135.

Plugged through: TBG

District: 02

Signed Michael R Wilson  
(TECHNICIAN)

INVOICED  
DATE 11-22-04  
SER. NO. 2005060833