

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-111-20423-00-00
Spot: NESWSWSW Sec/Twnshp/Rge: 22-18S-10E
454 feet from S Section Line, 459 feet from W Section Line
Lease Name: R & R RANCH Well #: 13-22
County: LYON Total Vertical Depth: 2453 feet

Operator License No.: 32886
Op Name: BURLINGTON RESOURCES OIL & GAS
Address: 717 TEXAS ST. #2100
HOUSTON, TX 77002

CIBP Size: feet: 2120
CIBP Size: feet: 2260
CIBP Size: feet: 2280
PROD Size: 5.5 feet: 2453 153 SX
SURF Size: 8.625 feet: 186 90 SX

\$79 72

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/09/2004 8:00 AM

Plug Co. License No.: 32006 Plug Co. Name: HURRICANE WELL SERVICE, INC.

Proposal Rcvd. from: KYLE HUDSON

Company: _____

Phone: (432) 688-6972

Proposed Plugging Method: SEE ATTACHED PLUGGING PROCEDURE AND WELL BORE DIAGRAM

Plugging Proposal Received By: MICHAEL HEFFERN

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 11/09/2004 5:00 PM

KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

ran tubing to 2118', pumped 35 bbl of mud, 25 sxs cement @ 2118 to 1898', pulled tubing out, shot casing @ 1412', pumped 30 bbl. Of mud, 25 sxs cement, @ 1326', pulled 2 joints of casing, pulled casing out, ran 8 joints of tubing to 249' pumped 85 sxs cement to surface, pulled tubing out.

Perfs:

Top	Bot	Thru	Comments
2299	2313		
2270	2271		
2264	2266		
2254	2255		
2246	2247		
2233	2234		
2097	2099		

RECEIVED
KCC DISTRICT #3

NOV 15 2004 MH

CHANUTE, KS

RECEIVED
NOV 19 2004
KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed

Michael Heffern

(TECHNICIAN)

INVOICED
DATE 11-22-04
INV. NO. 2005060834