

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-031-21967-00-00
Spot: SWNENENW Sec/Twnshp/Rge: 30-19S-14E
489 feet from N Section Line, 2147 feet from W Section Line
Lease Name: SLEAD Well #: 21-30
County: COFFEY Total Vertical Depth: 1897 feet

Operator License No.: 32886
Op Name: BURLINGTON RESOURCES OIL & GAS
Address: 717 TEXAS ST. #2100
HOUSTON, TX 77002

CIBP Size: feet: 1490
CIBP Size: feet: 1510
CIBP Size: feet: 1530
CIBP Size: feet: 1720
PROD Size: 5.5 feet: 1897 150 SX
SURF Size: 8.625 feet: 180 91 SX

#6165

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/08/2004 8:00 AM
Plug Co. License No.: 32006 Plug Co. Name: HURRICANE WELL SERVICE, INC.
Proposal Rcvd. from: KYLE HUDSON Company: _____ Phone: (432) 688-6972

Proposed Plugging Method: PER INSTRUCTIONS FROM DIST 03 OFFICE

Plugging Proposal Received By: MICHAEL HEFFERN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/08/2004 5:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

ran tubing o 1487', mixed 25 bbl. Of mud, mixed 25 sxs cement @ 1487' to 1267', pulled tubing out, shot casing @ 1026', pulled 2 joints, pumped 20 bbl of mud, pumped 25 sxs cement, pulled casing out, ran 8 joints of tubing to 249', pumped 85 sxs cement to surface. Pulled tubing out.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 1725 | 1726 | | SPF |
| 1708 | 1709 | | SPF |
| 1518 | 1519 | | SPF |
| 1495 | 1496 | | SPF |
| 1482 | 1483 | | SPF |

RECEIVED
KCC DISTRICT #3

NOV 15 2004 MH

CHANUTE, KS

RECEIVED
NOV 19 2004
KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

INVOICED

Signed

Mike Heffern
(TECHNICIAN)

DATE 11-22-04
SER. NO. 2005060834