

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-155-21361-00-00
Spot: NESE Sec/Twnshp/Rge: 11-25S-9W
1980 feet from S Section Line, 660 feet from E Section Line
Lease Name: BIGGERSTAFF Well #: 3-11
County: RENO Total Vertical Depth: 3998 feet

Operator License No.: 3911
Op Name: RAMA OPERATING CO., INC.
Address: 101 S. MAIN
STAFFORD, KS 67578

PROD Size: 5.5 feet: 3996 145 SX CMT
SURF Size: 8.625 feet: 201 190 SX CMT

\$ 129⁹⁴

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/04/2004 10:45 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-8088

Proposed Plugging Method: See actual report.

RECEIVED
KCC DISTRICT #2
NOV 10 2004
WICHITA, KS

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: PARTIAL
Date/Time Plugging Completed: 11/04/2004 12:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Sanded perforations to 3800' and put 5 sacks of cement on top. Cut casing off at 2400'. Pulled to 1400' and pumped 35 sacks of cement with cotton hulls. Pulled casing to 800' and pumped 35 sacks of cement with cotton hulls. Pulled casing to 250' and circulated cement to surface.

60/40 posmix with 4% gel.

Allied Cement #20177

Perfs:

Top	Bot	Thru	Comments
3872	3878		
3852	3858		

RECEIVED
NOV 19 2004
KCC WICHITA

Remarks:

Plugged through: CSG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

INVOICED
DATE 11-22-04
INV. NO. 2005060839