

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-191-21913-00-01
Spot: SESESW Sec/Twnshp/Rge: 7-30S-2W
300 feet from S Section Line, 2970 feet from E Section Line
Lease Name: SUSIE DUNCAN Well #: 1 SWD
County: SUMNER Total Vertical Depth: 4107 feet

Operator License No.: 5822
Op Name: VAL ENERGY, INC.
Address: PO BOX 116
WICHITA, KS 67201

PROD Size: 5.5 feet: 4107 100 SX CMT
SURF Size: 8.625 feet: 347 225 SX CMT

\$133⁴⁸

Well Type: SWD UIC Docket No: D26663.0 Date/Time to Plug: 11/02/2004 1:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SPOT 10 SX CMT PLUG ON BOTTOM, SHOOT OFF PIPE & PULL, SPOT 35 SX PLUG @ 525' & CMT TO SURF.

RECEIVED
KCC DISTRICT #2
NOV 4 - 2004

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL
Date/Time Plugging Completed: 11/02/2004 1:00 PM KCC Agent: STEVE VANGIESON

WICHITA, KS

Actual Plugging Report:

The open hole was sanded back to 4045' and capped with 5 sacks of cement. Recovered 5-1/2" from 3060'. Pulled to 600' and spotted 35 sacks of cement. Pulled 5-1/2" to 400' and spotted 35 sacks of cement. Pulled 5-1/2" to 250' and circulated cement to surface.

60/40 posmix with 4% gel

Allied Cementing #18075

Perfs:

Top	Bot	Thru	Comments
4106	4107	OH	


RECEIVED
NOV 19 2004
KCC WICHITA

Remarks:

Plugged through: CSG

District: 02

Signed _____



(TECHNICIAN)

INVOICED
DATE 11.22.04
INV. NO. 2005060840