

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-035-24205-00-00  
Spot: NESW Sec/Twnshp/Rge: 31-30S-8E  
1980 feet from S Section Line, 2218 feet from W Section Line  
Lease Name: FERGUSON RANCH Well #: 12-31  
County: COWLEY Total Vertical Depth: 3115 feet

Operator License No.: 32977  
Op Name: DORADO GAS RESOURCES LLC  
Address: 14550 EAST EASTER AVE., STE 1000  
CENTENNIAL, CO 80112

SURF Size: 8.625 feet: 420

# 101.24

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/14/2004 1:30 AM  
Plug Co. License No.: 32854 Plug Co. Name: GULICK DRILLING CO., INC.  
Proposal Rcvd. from: RON GULICK Company: GULICK DRILLING CO., INC. Phone: (620) 583-5804

Proposed 480' & 35 sxs  
Plugging 60' & 25 sxs  
Method: 15 sxs in rathole

**RECEIVED**  
**KCC DISTRICT #2**  
**NOV 15 2004**  
**WICHITA, KS**

Plugging Proposal Received By: JACK LUTHI WitnessType: NONE  
Date/Time Plugging Completed: 11/14/2004 3:00 AM KCC Agent: JACK LUTHI

**Actual Plugging Report:**

**Perfs:**

Filled bore with heavy mud. Ran drill pipe to 480' and pumped 35 sacks of cement. Pulled to 60' and pumped 25 sacks of cement to surface. Pumped 15 sacks of cement in rathole.  
  
60/40 posmix with 4% gel  
  
Consolidated #2325

**RECEIVED**  
**NOV 19 2004**  
**KCC WICHITA**

Remarks:

Plugged through: DP

District: 02

Signed Jack Luthi  
(TECHNICIAN)

**INVOICED**  
DATE: 11-22-04  
INV. NO. 2005060836