

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-147-20362-00-00  
Spot: CW2NENE . Sec/Twnshp/Rge: 14-5S-20W  
4620 feet from S Section Line, 990 feet from E Section Line  
Lease/Unit Name: RUNDLE Well Number: 1  
County: PHILLIPS Total Vertical Depth: 3480 feet

Operator License No.: 9559 Conductor Pipe: Size feet: 11310  
Op Name: PATTERSON, JERRY DBA PATTERSON Surface Casing: Size 8.625 feet: 212 135 SX CMT  
Address: PO BOX 307 Production: Size 4.5 feet: 3479 150 SX CMT  
LOGAN, KS 67646 Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 12/11/2002 10:00 AM  
Plug Co. License No.: 9559 Plug Co. Name: PATTERSON, JERRY DBA PATTERSON, JERRY OIL  
Proposal Rcvd. from: JERRY PATTERSON Company: PATTERSON, JERRY DBA PATTERSON Phone: (785) 689-4897

Proposed Plugging Method: According to KCC Rules & Regulations.  
Ordered 235 sxs cement and 600# hulls.  
Perforate at 1675' and 1025'.

Plugging Proposal Received By: HERB DEINES Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 12/11/2002 11:00 AM KCC Agent: ROGER MOSES

**Actual Plugging Report:**

8 5/8" S.P. at 212' w/135 sxs cement. 4 1/2" casing at 3479' w/150 sxs cement.  
Tied to 4 1/2" casing and squeezed with 125 sxs cement and 450# hulls.  
Max. P.S.I. 500#. S.I.P. 100#.  
Tied to 8 5/8" x 4 1/2" annulus - squeezed with 35 sxs cement and 150# hulls.  
Max. P.S.I. 250#. S.I.P. 100#.  
Total of 160 sxs 60/40 pozmix with 10% gel and 600# hulls.  
Dakota at 710' - 1010'. Anhy. At 1634' - 1669'.

RECEIVED  
JAN 03 2003  
KCC WICHITA

Remarks: SWIFT SERVICES CEMENT. TRACY TANK-WATER.

Plugged through: CSG

District: 04

Signed

ROGER L. MOSES  
(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 1-6-03

WV. NO. 2003061039

DEC 30 2002

replacement card

OZARK ENTERPRISES  
LOGAN KS

14-05S-20W  
C W/2 NE NE

#1 RUNDLE

site: 2-1/4 S & 1-1/4 E OF LOGAN KS  
contr: HELBERG OIL CO

dy: PHILLIPS  
field: HANSEN

API 15-147-20362

date 10/09/81    spd date 10/16/81    drig comp 10/22/81    card issued 04/01/00    last revised 09/14/98


ELV: 2115 KB LOG

tops.....	depth/datum
ANH.....	1634 + 481
B/ANH.....	1669 + 446
TOP.....	3017 -902
HEEB.....	3214 -1099
TOR.....	3240 -1125
LANS.....	3256 -1141
BKC.....	3459 -1344
RTD.....	3480 -1365

**IP status:**  
**OIL, P 6 BO & 10 BWPD, LKC 3256-3266, 03/26/82**  
 INFO RELEASED: 9/14/98 - WAS. OIL WELL - TEMP  
 COMP  
 CSG: 8-5/8" 212, 4-1/2" 3479  
 NO CORES  
 DST (1) 3226-3360 (TOR, LANS A), / 30-30-45-45, REC 90'  
 HG & OCM, 90' G & OCM    ISIP 713# FSIP 689# IFP  
 71# -71# FFP 107# -119# IHP 1726# FHP 1691# BHT 112  
 MICT - CO, PF (LANS A) 3256-3266 (EST), AC 250 GAL  
 (MA), & 1000 GAL (15%), ONFU 600' FL (200' OIL), POP,  
 P 6 BO & 10 BWPD, 3/26/82 - NO OTHER INFO  
 AVAILABLE

COPYRIGHT 1998  
INDEPENDENT OIL & GAS SERVICE, INC.  
WICHITA, KANSAS