

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-23208-00-~~10~~02
Spot: NESWNW Sec/Twnshp/Rge: 24-19S-14W
3630 feet from S Section Line, 4290 feet from E Section Line
Lease Name: NUSS D Well #: 2
County: BARTON Total Vertical Depth: 3580 feet

Operator License No.: 5004
Op Name: VINCENT OIL CORPORATION
Address: 125 N. MARKET, STE 1075
WICHITA, KS 67202

PROD Size: 5.5 feet: 3579 175 SX CMT
SURF Size: 8.625 feet: 772 300 SX CMT

116 35

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/27/2004 11:15 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD HIEBSCH Company: QUALITY WELL SERVICE, INC. Phone: (316) 262-3573

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS WitnessType: NONE
Date/Time Plugging Completed: 09/27/2004 12:45 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Sanded to 3291' and dumped 5 sxs cement.
Cut off casing at 1820'.
Pulled to 1550' and pumped 100 sxs 60/40 pozmix - 10% gel cement with 300# hulls.
Pulled to 850' and pumped 40 sxs cement with 100# hulls.
Pulled to 250' and circulated with 30 sxs cement.

Perfs:

Top	Bot	Thru	Comments
3355	3357		
3336	3342		
3319	3323		

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

ND.

Signed *Case Morris*
(TECHNICIAN)

INVOICED
DATE 10-14-04
NO. 2005060659

OCT 05 2004

VINCENT OIL CORPORATION

125 N. MARKET, #1110

#2 "D" NUSS


24-19-14W

WICHITA, KS 67202

NE SW NW

CONTR MALLARD DRILLING CO., INC. CTY BARTON

GEOL PAUL HAGEMER FIELD ESS



ELV 1872 KB SPD 8/26/83 CARD ISSUED 1/19/84 IP OIL WELL
 1864 GL KC 3334-3376 OA
 API 15-009-23,208

LOG	Tops	Depth/Datum
*ANH	755	+1117
*B/ANH	783	+1089
TOP	2748	- 876
OREAD	2994	-1122
HEEB	3085	-1213
TOR	3100	-1228
BR LM	3180	-1308
LANS	3193	-1321
STARK	3364	-1492
BKC	3420	-1548
CONG CHT	3468	-1596
ARB DOL	3500	-1628
LTD	3575	-1703
RTD	3580	-1708
*SAMPLE TOPS		

8 5/8 " 772/300 SX; 5 1/2 " 3579/175 SX
 DST (1) 3305-3366 (LKC) / 30-60-60-60, 205' GIP, REC 15' O & GCMW (7% OIL, 25% G, 25% M, 43% W), 120' GCMW, 240' MW, 300' SW, SIP 948-914#, FP 69-196 / 243-370#
 DST (2) 3388-3430 (PENN) / 30-15-15-15, REC 10' M, SIP 57-57#, FP 46-46 / 46-57#
 DST (3) 3330-3364 (LKC, W / STR PKR) / 30-45-45-60, 55' GIP, REC 185' GCMW, 450' SW, ISIP 914#, FSIP NO READING, FP 92-196 / 254-355#
 MICT - CO, PF (ARB) 3525-26, SWB DRY, NS, SION, FU 3250' FL, SWB 4.4 BF/4 HRS (100% WTR), PF (ARB) 3506-3510, SWB DWN, NS, ONFU 2625' FL, SWB ALL WTR, NS, SWB 1.17 BF PER 30" (100% WTR)/3 HRS, SET CIBP AT 3405, PF (LKC) 3376-79, SWB DRY, AC 500 G (15% MA), SWB PT LD, SION, FU 1575' FL (5' OIL ON TOP), SWB DWN, SO, SI, FU 2300' FL (15' OIL ON TOP), SI, FU 1650' FL (35' OIL ON TOP), SWB DWN, SO, SET RBP AT 3365', PF (LKC) 3334-36, SWB DRY, AC 500 G (15% MA), SWB 41.81 BF (APPX 10% OIL)/1 HR, SI, FU 2725' FL (55' OIL ON TOP), SWB DWN, SO, PULLED RBP, SWB 7.07 BF (6% OIL)/30", SI, FU 2800' FL (45' OIL ON TOP), SWB DWN, SO, T & R, POP, OIL WELL 10/15/83

COPYRIGHT 1983
 INDEPENDENT OIL & GAS SERVICE, INC.
 WICHITA, KANSAS