


STATE OF KANSAS
STATE CORPORATION COMMISSION

15-147-00643-00-00

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Phillips County, Sec. 2 Twp. 5 Rge. 20 (E) (W) W
Location as "NE/CNW/SW" or footage from lines SW NW NW
Lease Owner D. L. Somers
Lease Name Hockett Well No. 2
Office Address Norton, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed December 30 19 60
Application for plugging filed December 29 19 60
Application for plugging approved December 29 19 60
Plugging commenced December 29 19 60
Plugging completed December 30 19 60
Reason for abandonment of well or producing formation Too low structurally

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3403 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	187.87'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 550'. Set plug. Put in 20 sacks cement. Filled to 180'. Set plug. Put in 15 sacks cement. Filled with heavy mud to 40'. Set plug. Filled to top with 1 sack hulls and 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

JAN 25 1961

CONSERVATION DIVISION
Wichita, Kansas

1-25-61

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor C-G Drilling Co.
Address 107 Rule Building, Wichita 2, Kansas


STATE OF KANSAS COUNTY OF SEDGWICK, ss.
G. F. Galloway (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) G. F. Galloway
107 Rule Building
(Address)

SUBSCRIBED AND SWORN to before me this 5th day of January, 1961

My commission expires May 20, 1963

Vicky Jacobs
Notary Public.



15-147-00643-00-00

W E L L L O G

OPERATOR D. L. Somers SEC. 2-5-20W
 WELL NAME Hockett #2 LOC. SW NW NW
 TOTAL DEPTH 3403' COUNTY Phillips
 COMM. December 20, 1960 COMP. December 30, 1960 STATE Kansas
 RIG NO. 1 ELEVATION 1961' R.B.
 CASING: Ran 187.87' (9 jts.) 8-5/8" OD Surface PRODUCTION: D & A
 Casing.

All measurements taken from the top of rotary bushing.

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
0	165	Sand		
165	560	Shale		
560	800	Sand		
800	1010	Sand-Shale		
1010	1200	Sand		
1200	1483	Red Bed		
1483	1525	Anhydrite		
1525	2375	Shale-Shell	0° - 2500	
2375	2935	Shale-Lime	0° - 2750	
2935	3100	Lime-Shale	0° - 3000	
3100	3220	Lime		DST 3113-3143'
3220	3300	Lime-Shale	0° - 3250	DST 3141-3160'
3300	3375	Lime		DST 3159-3183'
3375	3403	Lime-Shale		

RECEIVED
STATE CONSERVATION COMMISSION

JAN 25 1961

CONSERVATION DIVISION
Wichita, Kansas

1-25-61

STATE OF KANSAS }
 COUNTY OF SEDGWICK } SS.

The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.

By G. F. Galloway
G. F. Galloway

SUBSCRIBED AND SWORN TO, BEFORE ME, THIS 5th day of January, 1961.

My commission expires:
MAY 20, 1961

Vicky Jacobs
Vicky Jacobs - Notary public