

15-147-00097-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Phillips

County. Sec. 2 Twp. 5 Rge. (E) 20 (W)

Location as "NE/CNW 1/4 SW 1/4" or footage from lines NE SE NW

Lease Owner White Eagle Oil Company

Lease Name WILTROUT

Well No. 1

Office Address First National Bldg. Tulsa 3, Okla.

Character of Well (completed as Oil, Gas or Dry Hole) Dryhole

Date well completed 1-4-1952 19

Application for plugging filed " 19

Application for plugging approved " 19

Plugging commenced 1-24-1952 19

Plugging completed 1-30-1952 19

Reason for abandonment of well or producing formation Dryhole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty

Producing formation Depth to top Bottom Total Depth of Well 3233 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Heebner	dry	3082	-1100	10-3/4"	183	none
Lansing		3107	-1125	5-1/2"	3232	2535

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Shot pipe (5-1/2") off at 2535', pulled pipe and mudded hole to 184' Dumped 20 sacks of cement at 184', finished mudding hole and put 10 sacks cement at surface.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Helmerich & Payne, Inc. % Harry Saye
Address First National Bldg. Tulsa 3, Oklanoma.

STATE OF Oklahoma, COUNTY OF Tulsa, ss.

Harry Saye (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Harry Saye

First National Bldg. Tulsa 3, Okla.

(Address)

SUBSCRIBED AND SWORN to before me this 25th day of February 19 52

[Signature]

Notary Public.

My commission expires 8-29-1955.

22-5138-s 9-48-10M
FEB 28 1952
CONSERVATION DIVISION
Wichita, Kansas

2-28-52

PLUGGING
FILE SEC 2 T 5 R 20W
144-43

DRILLER'S

LOG

Company: White Eagle Oil Company

NE $\frac{1}{4}$ SE $\frac{1}{4}$ NW $\frac{1}{4}$
Sec. 2, Twp. 5S, Rge. 20W

Farm: Wiltrot
Comm: 12-2-51

Well No. 1
Comp: 12-13-51

County: Phillips,
Kansas

Total Depth: 3233'
Contractor: Peel Brothers, Inc.,
Casing:

Elevation:

10 3/4" O.D. @ 183' cem.
5 1/2" @ 3232' cem.

Production:

The figures below indicate bottom of formations

Soil and Sand	0'	35
Rock and Shells		80
Sand		120
Shale and Shells		700
Sand		725
Shale and Sand		825
Shale and Shells		1110
Sand		1220
Shale		1455
Shale and Shells		1700
Shale		1765
Shale and Shells		2110
Shale and Lime		2210
Lime		2240
Lime and Shale		2245
Shale and Shells		2580
Shale, Lime and Shells		2935
Shale and Lime		3003
Lime		3065
Lime and Shale		3140
Lime		3233
Total Depth		3233

This is to certify that the above information is to the best of my knowledge true and correct.

PEEL BROTHERS, INC.,

BY: Mendell E. Peel

SUBSCRIBED AND SWORN to before me this 14th day of December, 1951.

Bernard A. Irwin
Notary Public - Barton County, Kansas.

My commission expires April 23, 1955.

PLUGGING
FILE SEC-2-T-5-R-20
BOOK PAGE 140 LINE 43