

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2070
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R. 482-3-117

API NUMBER 15-135-24311-0000

LEASE NAME Miner

WELL NUMBER 1
1,980 Ft. from ^N Section Line
990 Ft. from E Section Line

SEC. 20 TWP. 19 NOR. 23 R. W

COUNTY NESS

Date Well Completed 11-5-04

Plugging Commenced 11-5-04

Plugging Completed 11-5-04

TYPE OR PRINT
NOTICE: Fill out completely
and return to Comm. Div.
office within 30 days.

LEASE OPERATOR CARMEN SCHMITT, INC.

ADDRESS PO BOX 47, GREAT BEND, KS 67530

PHONE# (620) 793-5100 OPERATORS LICENSE NO. 6,569

Character of Well D & A

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11-05-04 (date)

by Mike Maier (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom T.O. 4,435'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	217'	Cmtd. w/150 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each section. Push plug to 1,600', pump 50 sax cement on plug thru drill pipe; push plug to 850', pump 80 sax cement on plug thru drill pipe; push plug to 400', pump 40 sax cement on plug thru drill pipe; push plug to 220', pump 40 sax cement on plug thru drill pipe; push plug to 40', dump 10 sax cement on plug to cellar; dump 15 sax cement down rat hole and 10 sax down mouse hole.

Name of Plugging Contractor SHIELDS DRILLING CO. License No. 5184

Address BOX 709, RUSSELL, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: CARMEN SCHMITT, INC.

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Jack P. Beeman, Sec.-Treas. Contractor

(Employee of ~~Operator~~ or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed in the same are true and correct, so help me God.

(Signature) Jack P. Beeman

(Address) Box 709, Russell, KS 67665

SUBSCRIBED AND SWORN TO before me this 12th day of November, 2004

Leeth Phillips
Notary Public

My Commission Expires:



RECEIVED
NOV 17 2004
KCC WICHITA