

LEASE NAME J M Coberly 'A'

WELL NUMBER #1

3300 Ft. from S Section Line

1980 Ft. from ^W Section Line

SEC. 2 TWP. 15S RGE. 28W (X) or (W)

COUNTY Gove

Date Well Completed

Plugging Commenced 10/5/04

Plugging Completed 10/5/04

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Whitetail Crude, Inc

ADDRESS P O Box 544, Ness City, KS 67560-0544

PHONE () 785-798-3641 OPERATORS LICENSE NO. 31627

Character of Well oil

Well (Oil, Gas, D&A, SWD, Input, Water Supply Well)

A plugging proposal was approved on 10/4/04

Roger Moses (KCC District Agent's Name)

ACQ-1 filed? unknown If not, is well log attached? sent with CP-1

Producing Formation LKC Depth to Top Bottom T.D. 4149

Show depth and thickness of all water, oil and gas formations.

WELL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	291	-0-
				4 1/2	4054	713

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug material used, state the character of same and depth placed, from feet to feet each set.
Ran tubing to 2280' & spotted 35 sk cement plug w/300# hulls. Pulled tubing out of well.
Cut 4 1/2" casing off @ 713', pulled 4 1/2" up to 650' and spotted 35 sk plug. Pulled 4 1/2" up to 328' and circulate 50 sk cement to surface. Pulled 4 1/2" out and topped off 8 5/8" w/30 sk cement. Job complete.


Name of Plugging Contractor Whitetail Crude, Inc License No. 31627

Address P O Box 544, Ness City, KS 67560-0544

Name of Party Responsible for Plugging Fees: Whitetail Crude, Inc

Date of 11/16/04 County of Ness, ss.

Mike J. Fritzler, President Whitetail Crude, Inc (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed. That the same are true and correct, so help me God.



(Signature) Mike J. Fritzler
Mike J. Fritzler, President
(Address) P O Box 544, Ness City, KS 67560-0544

SUBSCRIBED AND SWORN TO before me this 16th day of November 2004, XXX

Debra Kerr Notary Public

My Commission Expires: 4/20/05

USE ONLY ONE SIDE OF EACH FORM

RECEIVED
NOV 17 2004
KCC WICHITA

Bur