

LEASE NAME Schultz SWD

WELL NUMBER #1

4620 Ft. from S Section Line

1320 Ft. from E Section Line

SEC. 6 TWP. 20S RGE. 15W ~~XXX~~ (W)

COUNTY Barton

Date Well Completed 8/3 *KCC BEN 11/16/04 RBDM*

Plugging Commenced 10/12/04 *11/16/04 RBDM*

Plugging Completed 10/13/04

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Whitetail Crude, Inc

ADDRESS P O Box 544, Ness City, KS 67560-0544

PHONE ( ) 785-798-3641 OPERATORS LICENSE NO. 31627

Character of Well SWD

Oil, Gas, D&A, SWD, Input, Water Supply Well *RBDM*

A plugging proposal was approved on 10/13/04 *KCC BEN 11/16/04*

Herb Deines (KCC District Agent's Name).

ACO-1 filed? unknown If not, is well log attached? no log received when purchased in 1993

Producing Formation Arbuckle SWD Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. PBTD 3754' *RBDM KCC 3775' BEN 11/16/04*

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In,	Pulled out
				8 5/8	660'	-0-
				4 1/2	3754	1758'

RECEIVED  
NOV 18 2004  
KCC WICHITA

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug material used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.  
10/12/04 Sanded well off to 3690'; capped sand plug w/4 sk cement via dump bailer. 10/13/04 Shot casing off @ 1758', lifted pipe up & spotted an 85 sk plug w/300# hulls @ 1750. Pulled casing to 1075' & spotted 40 sk plug w/100# hulls. Pulled casing to 700' & spotted 40SK plug w/100# hulls. Pulled to 350' & circulated 65 sk cement to surface. Pulled 4 1/2" out, topped off 8 5/8" with 25 sk cement. Job complete.


Name of Plugging Contractor Whitetail Crude, Inc License No. 31627

Address P O Box 544, Ness City, KS 67560-0544

Name of Party Responsible for Plugging Fees: Whitetail Crude, Inc

Date of 11/15/04 County of Ness, ss.

Mike J. Fritzier, President Whitetail Crude, Inc (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.



(Signature) Mike J. Fritzier  
Mike J. Fritzier, President  
(Address) P O Box 544, Ness City, KS 67560-0544

SUBSCRIBED AND SWORN TO before me this 15th day of November, 2004, X

Debra Kerr  
Debra Kerr Notary Public

My Commission Expires: 4/20/05

USE ONLY ONE SIDE OF EACH FORM

*Ber*