


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Phillips County. Sec. 4 Twp. 5S Rge. 20W (E) (W)
Location as "NE/CNW/SW" or footage from lines C NW SE SW
Lease Owner Helmerich & Payne, Inc.
Lease Name Hofaker Well No. 1
Office Address Box 558 Garden City, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 9-27-64 19__
Application for plugging filed 9-27-64 19__
Application for plugging approved 9-27-64 19__
Plugging commenced 9-27-64 19__
Plugging completed 9-27-64 19__
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19__
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3510 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FRGM	TD	SIZE	PUT IN	PULLED OUT
		212	0	8-5/8"	212	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

3510' to 480' Heavy Drilling Mud
480' to 420' Plug and 20 sks cement
420' to 180' Heavy Drilling Mud
180' to 120' Plug and 20 sks cement
120' to 30' Heavy Drilling Mud
30' to 0 Plug and 10 sks cement

PLUGGING COMPLETED 9:05 PM 9-27-64

RECEIVED
STATE CORPORATION COMMISSION

OCT 1 - 1964

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Chemical & Technical services Inc.
Address Hill City, Kansas

10-1-64

STATE OF Kansas, COUNTY OF Finney, ss.
C. A. Richter (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. A. Richter

Box 558 Garden City, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 29 day of September, 1964

My commission expires July 1968

Robert N. Boyd
Robert N. Boyd Notary Public.

CONTRACTOR'S WELL LOG

CONTRACTOR:	CHEMICAL & TECHNICAL SERVICES, INC.
OWNER:	HELMERTICH & PAYNE, INC.
WELL:	GEORGE HOFAKER #1
LOCATION:	NW SE SW SEC. 4-5S-20W PHILLIPS CO., KANSAS
COMMENCED:	9/18/64
COMPLETED:	9/27/64

15-147-00161-00-00

0	60	CLAY & SAND	ELEVATION:	GROUND LEVEL	1966'
60	213	SANDY SHALE & SHALE		DERRICK FLOOR	1971'
213	1000	SHALE & SAND		KELLY BUSHING	1973'
1000	1065	SHALE			
1065	1240	SAND	ELECTRIC LOG TOPS:		
1240	1509	SHALE SAND & RED BED			
1509	1537	ANHYDRITE	HEEBNER	3119'	(-1146)
1537	1890	SHALE	TORONTO	3147'	(-1174)
1890	2370	SHALE & LIME	LANSING	3166'	(-1193)
2370	3135	LIME & SHALE	BASE KANSAS CITY	3355'	(-1382)
3135	3255	LIME	ARBUCKLE	3454'	(-1481)
3255	3328	SHALE & LIME			
3328	3441	LIME			
3441	3510	LIME & SHALE			
	3510	ROTARY TOTAL DEPTH			

SET 7" CASING @ 212' W/170 SACKS CEMENT

DRY & ABANDONED

WE HEREBY CERTIFY THIS TO BE A CORRECT AND ACCURATE LOG OF THE ABOVE DESCRIBED WELL, AS SHOWN ON THE DAILY DRILLING REPORTS.

CHEMICAL & TECHNICAL SERVICES, INC.

BY: *D. F. McCarty*
ASST. TREASURER

SUBSCRIBED AND SWORN TO BEFORE THIS 29th DAY OF SEPTEMBER, 1964.

Paula S. Lewis
NOTARY PUBLIC

My Commission Expires January 20, 1968

RECEIVED
STATE CORPORATION COMMISSION

NOV 19 1964

CONSERVATION DIVISION
Wichita, Kansas