

15-147-00094-06-00


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

PHILLIPS County. Sec. 10 Twp. 5S Rge. 18 ~~25~~ (W)  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE NE NW  
Lease Owner Francis Oil & Gas, & Pickrell Drilling Company, Inc.  
Lease Name PARKER Well No. 1  
Office Address 705 Fourth National Bank Building, Wichita 2, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 7/28 19 50  
Application for plugging filed 7/27 19 50  
Application for plugging approved 7/28 19 50  
Plugging commenced 7/28 19 50  
Plugging completed 7/28 19 50  
Reason for abandonment of well or producing formation Dry & Abandoned.

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation Depth to top Bottom Total Depth of Well 588 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	123'	None
				No oil string run.		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud from 3588' to 110'. Set bridge at 110' and filled with 47 sacks cement to bottom of cellar.

RECEIVED

Conservation Div.  
08-09-50  
AUG 9 - 1950

STATE CORPORATION  
COMMISSION  
KANSAS

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Pickrell Drilling Company, Inc.  
Address 705 Fourth National Bank Bldg., Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Joseph B. Brungardt, Jr. (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Joseph B. Brungardt, Jr.  
705 Fourth Natl Bank Bldg., Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of August, 19 50.

Ethel Zimmerman  
Notary Public.

My commission expires January 28, 1953

PLUGGING  
FILE SEC 10 T 5 R 20  
BOOK PAGE 19 LINE 38

COMPANY: FRANCIS OIL AND GAS INC. Rotary Drilling commenced: July 19, 1950.  
 PICKRELL DRILLING COMPANY, INC. Rotary Drilling completed: July 28, 1950.

LOCATION: FARM #1, NE NE SW Sec. 10-56-18W  
 Phillips County, Kansas.

CONTRACTOR: PICKRELL DRILLING COMPANY, INC.  
 Wichita, Kansas

CASING DEPTH: 123' (3 jts.) 8 5/8" surface casing set at 123' in a 12 1/2" hole,  
 cemented with 75 sacks cement.

Drilled 7 7/8" hole from 123' to 3553' T.D. No oil string run.

LOG

(Figures indicate bottom formation - measurements from top rotary casing.)

Cellar	5	Circulate for samples at 3150'
Chalk	73	" " " " 3210'
Shale	125	" " " " 3275'
Shale & Shells	695	" " " " 3420'
Sand	1165	" " " " 3495'
Shale & Shells	1335	" " " " 3507'
Sand	1455	" " " " 3522'
Anhydrite	1495	" " " " 3557'
Shale	1510	" " " " 3560'
lime & shale	2100	
Shale	2205	Slope test at 1500' - 0° off.
lime & shale	2415	" " " 1500' - 0° off.
Shale	2835	" " " 2500' - 0° off.
lime & shale	3040	" " " 2500' - 0° off.
lime	3553 Rotary T.D.	" " " 3500' - 0° off.

GEOLOGICAL DATA

Elevation	1979 D.F.
Anhydrite	1465
Neohar	3112
Turcite	3135
Lensing	3152
Conglomerate	3495
Archele	3500

S.L.N. at 3000' - O.K.  
 " " " 3525' - O.K.

Lost circulation at 315'.

Drill Stem Test at 3526 - 10',  
 Open 30 min - recovered 15' cut.

Filled hole with heavy mud from 3550' to 110'. Set bridge at 110' and filled with 47 sacks cement to bottom of cellar.

The undersigned, Joseph B. Brungardt, Jr., Assistant Secretary of PICKRELL DRILLING COMPANY, INC., hereby certifies in behalf of said corporation, that the above log is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY, INC.

By Joseph B. Brungardt, Jr.  
 Assistant - Secretary.

STATE OF KANSAS }  
 COUNTY OF WAGONER } SS

BE IT REMEMBERED that on this 3rd day of August, 1950, before me, the undersigned, a Notary Public, duly commissioned, in and for the county and state aforesaid, came Joseph B. Brungardt, Jr., Assistant Secretary of Pickrell Drilling Company, Inc., a corporation of the State of Kansas, personally known to me to be such officer, and to be the same person who executed as such officer the foregoing instrument of writing in behalf of said corporation, and he duly acknowledged the execution of the same for himself and for said corporation.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal on the day and year last above written.

My commission expires January 28, 1951.

Ethel J. Zimmerman  
 RECEIVED  
 Conservation Div.  
 AUG 9 - 1950  
 STATE CORPORATION  
 COMMISSION  
 KANSAS

PLUGGING  
 FILE SEC 10-5-18W  
 BOOK PAGE 18 LINE 38