

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15 147 20460 - 0000

API NUMBER _____

LEASE NAME ARMSTRONG

WELL NUMBER 4

4660 north Ft. from S Section Line

4950 west Ft. from E Section Line

SEC. 2 TWP. 5s RGE. 19w (E) or (W)

COUNTY PHILLIPS

Date Well Completed oct 30 1984

Plugging Commenced JULY 18 2003

Plugging Completed JULY 18 2003

JUL 31 2003

KCC WICHITA

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR JOHNSON OIL

ADDRESS 258 east highway 36 phillipsburg kansas 67661

PHONE# 785 543 6171 OPERATORS LICENSE NO. 3077

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on EMERGENCY PLUGGING (date)

by RODGER MOSES DISTRICT 4 (KCC District Agent's Name).

Is ACO-1 filed? yes if not, is well log attached? _____

Producing Formation lansing kansas city Depth to Top 3054 Bottom 3251 T.O. 3340

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
SURFACE CASING	rock	0	210	8 5/8	210	NONE
production tubing		0	3000	2 3/8	3000	none
production	lansing k/c	0	3329	4 1/2	3329	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each set tubing and packer set at 3000 feet with circulator collar and cast iron plug at 3000 feet started to pump cement down tubing began circulation between 2 inch and 4 1/2 cement began to circulate got ready for flush cast iron plug failed cement fell into our production zone. Called district 4 office for plugging orders

talked to mr mores tyed back onto tubing pumped 125 sacks and 300lbs huls circulated from 3000 to surface. then tyed onto surface with 50 sacks cement 200 huls plugged off tubing and pressured 600lbs shut in at 1501bs 4 1/2 and surface pressured 500lbs shut in at 1001bs job done.

Name of Plugging Contractor ALLIED CEMENTING RUSSELL KANSAS

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: JOHNSON OIL

STATE OF KANSAS COUNTY OF PHILLIPS, ss.

KEVIN JOHNSON OPERATOR (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Kevin Johnson
(Address) 258 EAST HIGHWAY 36

SUBSCRIBED AND SWORN TO before me this 28 day of July, 2003

[Signature]
Notary Public

My Commission Expires: 8-23-2005

Notary Public State of Kansas
Kimberly Beach
My Appt Exp 8-23-05
Form CP-1
Revised 05-88