

15-147-20366-00-00

WELL PLUGGING RECORD

Give All Information Completely  
 Make Required Affidavit

COUNTY Phillips SEC. 3 TWP. 5 RGE. 18 N/W  
 Location as in quarters or footage from lines:

1650 FWL & 330 FNL C NW/4 NE/4 NW/4 330'


Lease Owner Antares Oil Corporation

Lease Name Armstrong Foundation Well No. 1-3

Office Address 1667 Cole Blvd., Ste. 210

Character of Well (Completed as Oil, Gas or Dry Hole): DA

Date Well Completed 12-17-81

Application for plugging filed 12-17-81

Plugging commenced 12-17-81

Plugging completed 12-17-81

Reason for abandonment of well or producing formation DA

Locate Well  
 correctly on above  
 Section Platt.

Was permission obtained from the Conservation Division or it's  
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Marian Schmidt

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 3335'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud  
 fluid was placed and the method or methods used in introducing it into the hold. If cement  
 or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
 to \_\_\_\_\_ feet for each plug set.

Bottom Plug	840'	70 sax
Second plug	330'	40 sax
Solid Bridge	40'	10 sax
Rat hole		10 sax

RECEIVED  
 STATE CORPORATION COMMISSION

MAR - 8 1982

CONSERVATION DIVISION  
 Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton 3-8-82

STATE OF Colorado COUNTY OF Jefferson, ss.

John S. Nikonchik (employee of owner) or (owner or operator) of the  
 above-described well, being first duly sworn on oath, says: That I have knowledge of the  
 facts, statements, and matters herein contained and the log of the above-described well as  
 filed and that the same are true and correct. So help me God.

(Signature) John S. Nikonchik  
1667 Cole Blvd., Suite 210  
Golden, CO (Address) 80401

SUBSCRIBED AND SWORN TO before me this 7th day of Jan., 19 82

Carolyn D. Hepp  
 Carolyn D. Hepp, Notary Public.

My Commission expires: November 25, 1984

DESIGNATE TYPE OF COMP.: OIL, GAS,  
DRY HOLE, SWDW, ETC.:

Operator Antares Oil Corporation		
Well No. #1-3	Lease Name ARMSTRONG FOUNDATION	Dry hole
S <u>3</u> T <u>5</u> R <u>18</u> <del>K</del> W		

**WELL LOG**

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,  
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
DST #1 Lansing "A" (3090-3115, E-log) Op 30, SI 45, Op 45, SI 60 IHP 1603#, ISIP 1048#, FSIP 1009#, FHP 1574#, IFP 49-59#, FFP 68-78# Rec. 90' fluid - 85' MW, 5' SOCM	3087'	3112'	Anhydrite Bader Topeka Oread	1359 (+559) 2345 (-427) 2855 (-937) 3014 (-1096)
DST #2 Lansing "G" (3195-3213, E-log) Op 30, SI 45, Op 45, SI 60 IHP 1623#, ISIP 1184#, FSIP 1175#, FHP 1603#, IFP 59-354#, FFP 338-804# Rec. 5' free oil, 240' OCMW, 1505' SOCW	3192'	3210'	Heebner Lansing "A" Lansing "G" Lansing "H" Lansing "I" Lansing "J"	3056 (-1138) 3099 (-1181) 3196 (-1278) 3232 (-1314) 3254 (-1336) 3270 (-1352)
DST #3 Lansing "H" & "I" (3218-3269', E log) Op 30, SI 45, Op 45, SI 60 IHP 1635#, FHP 1604#, ISIP 1184#, FSIP 1153#, IFP None, tool plugged; FFP 83-114#. Rec. 3' free oil, 180' Heavily OCM, 30' OCM	3216'	3267'	Base KC  TD	3323 (-1405)  3338 (-1420)
DST #4 Lansing "J" (3262-3282', E-log) Op 30, SI 45, Op 45, SI 60 IHP 1701#, FHP 1623#, FSIP 1116#, FSIP 1145#, IFP 59-59#, FFP 68-68# Rec. 10' free oil, 35' OCM				
DST #5 Lansing "G" Straddle test (3195-3213', E-log) Op 30, SI 45, Op 45, SI 60 IHP 1623#, FHP 1603#, ISIP 1184#, FSIP 1175#, IFP 59-354#, FFP 338-804# Rec. 10' free oil, 300' OCMW, 1500' SOCW.				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	<p><i>Steve A. Hiraoka</i> Steve A. Hiraoka Signature</p> <p>Operations Engineer Title</p> <p>February 23, 1982 Date</p>
---------------	--

KANSAS

WELL COMPLETION REPORT AND DRILLER'S LOG


API No. 15 — 147 — 20,366 — 00-00  
County Number

S. 3 T. 5 R. 18 W

Loc. NW/4 NE/4 NW/4

County Phillips

640 Acres  
N



Locate well correctly

Elev.: Gr. 1912'

DF \_\_\_\_\_ KB \_\_\_\_\_

Operator  
Antares Oil Corporation

Address  
1667 Cole Blvd., Suite 210, Golden, CO 80401

Well No. #1-3 Lease Name ARMSTRONG FOUNDATION

Footage Location  
400 feet from (N) (S) line 1740' feet from (E) (W) line

Principal Contractor Circle M Drilling, Inc. Geologist Martin Dubois

Spud Date 12-5-81 Date Completed 12-17-81 Total Depth 3335' P.B.T.D.

Directional Deviation Oil and/or Gas Purchaser

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8-5/8"	24#	342' KB	Reg.	165	2% gel 3% cc

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

RECEIVED  
STATE CORPORATION COMMISSION  
MAR - 8 1982  
CONSERVATION DIVISION  
Wichita, Kansas

INITIAL PRODUCTION

Date of first production \_\_\_\_\_ Producing method (flowing, pumping, gas lift, etc.) \_\_\_\_\_

RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio
	bbls.	MCF	bbls.	CFPB

Disposition of gas (vented, used on lease or sold) \_\_\_\_\_ Producing interval (s) \_\_\_\_\_

3-8-82

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.