

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 6-11-84 15-147-01000-0001

LEASE NAME ARMSTRONG

WELL NUMBER 2

TYPE OR PRINT  
NOTICE: Fill out completely and return  
to Cons. Div. office within 30 days.

510 Ft. from S/W Line of Section (circle one)

1320 Ft. from E/W Line of Section (circle one)

LEASE OPERATOR JOHNSON OIL

SPOT LOCATION C-N/2 NE

ADDRESS BOX 35 RR 3

SEC. 3 TWP. 5S S. RGE 18W (E) or (W)

CITY, STATE, ZIP PHILLIPSBURG KANSAS 67661

COUNTY PHILLIPS

PHONE# 785-543-6171 OPERATORS LICENSE NO. 3077

Date Well Completed 6-11-84

Character of Well OIL WELL  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Plugging Commenced MARCH 16 2000

Date Plugging Completed MARCH 16 2000

The plugging proposal was approved on \_\_\_\_\_ (date)

by DENNIS HAMMEL DISTRICT 4 (KCC District Agent's Name)

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation(s) LANSING KANSAS CITY Depth to Top 3230- Bottom 3360 T.D. 3520

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
LANSING	oil	3235	3242	4 1/2	3520	none
K/C	OIL	3250-	3400	4 1/2	3520	none
SURFACE CASING				8 5/8	180 feet	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

Ran 2 inch tubing to 2900 spotted 8 sacks gel.

Then 25 sacks common and 200 lbs hals.

pulled up to 1400 circulated cement 80 sacks

pumped down 4 1/2 30 sacks 500 lbs shut in 40 sacks down annulus 200lbs shut in

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor ALLIED CEMENTING

License No. N/A

Address RUSSELL KANSAS

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: JOHNSON Oil

STATE OF KANSAS COUNTY OF PHILLIPS, ss.

KEVIN JOHNSON (Employee of Operator or (Operator) of above-described well, being first

duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Kevin Johnson to Johnson Oil

(Address) Box 35 RR 3 Phillips Kansas

SUBSCRIBED AND SWORN TO before me this 6th day of April, 19 2000

OSTERMAN  
Notary Public

My Commission Expires: 11 April 2001

Notary Public  
11 APR 2001

RECEIVED  
STATE CORPORATION COMMISSION

APR 10 2000

CONSERVATION DIVISION  
Wichita, Kansas