


15 147-00858-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Phillips County. Sec. 10 Twp. 5 Rge. (#) 20 (W)

Location as "NE/CNW/SW" or footage from lines \_\_\_\_\_  
Lease Owner Helmerich and Payne Inc.  
Lease Name Graham Well No. 1  
Office Address First Natl. Bldg. Tulsa 3 Okla.  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 11-7-57 19\_\_\_\_  
Plugging completed 11-27-57 19\_\_\_\_  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3457 feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10 3/4	160'	0'
				7"	3413'	1438'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged back with sand to 3200' and dumped 5 sax. cement with dump bailer from 3200' to 3170' Pulled casing to 1000' mixed and Circ. 40 sax. Magogel and 10 sax. Magobar with pump truck. Pulled casing to 600' mixed and pumped in 30 sax. cement with pump truck. Pulled casing to 160' mixed and pumped in 25 sax. cement with pump truck pulled remainder of casing. Bailed off mud to 30', set rock bridge from 30' to 20', mixed and poured 10 sax. cement from 20' to base of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Ace Pipe Pulling Co.  
Address Box 304 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Finney, ss.  
T. E. Mort (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) T. E. Mort  
Box # 255; Garden City, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 3 rd. day of December, 19 57

My commission expires 11/30/60  
Russell Wells Notary Public.

PLUGGING  
FILE SEC. 10 T. 5 R. 20  
BOOK PAGE 59 LINE 11

RECEIVED  
STATE CORPORATION COMMISSION  
12-4-57 DEC 4 1957  
CONSERVATION DIVISION  
Wichita, Kansas

15-147-00858-00-00

HELMERICH & PAYNE, INC.  
Box # 255  
Garden City, Ks.

RECEIVED  
STATE CORPORATION COMMISSION

FEB 20 1958

CONSERVATION DIVISION  
Wichita, Kansas

2-20-58

WELL LOG

Well No. 1  
Lease Graham  
Description NW NE NE 10-5-20W  
County Phillips

<u>Formation</u>	<u>Top</u>	<u>Bottom</u>
Surface clay and gravel	0	162
Sandy clay, shale and shells	162	1035
Shale, sand and shells	1035	1280
Red bed and shale	1280	1320
Lime and shale	1320	1425
Shale and shells	1425	1520
Anhydrite	1520	1550
Lime and shale	1550	1770
Shale and shells	1770	1875
Shale, line shells	1875	2020
Shale, lime	2020	2175
Lime and shale	2175	2438
Lime	2438	2443
Shale and lime	2443	2590
Lime	2590	2675
Shale and lime	2675	3130
Lime, hard	3130	3163
Cherty lime	3163	3188
Lime	3188	3215
Cherty lime	3215	3250
Lime	3250	3360
Lime and shale	3360	3405
Lime	3405	3416
TOTAL DEPTH	3416	

I, the undersigned, being first duly sworn upon oath, state that this well record is true, correct and complete according to the records of this office and to the best of my knowledge and belief.

*J.E. Mout*

Prod. Supt.

Subscribed and sworn to before me this 19th day of February, 1958

My commission expires 11/29/60

*Russell Wells*  
Russell Wells - Notary Public

PLUGGING  
FILE SEC 10 T 5 R 204  
BOOK PAGE 59 LINE 11