

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: American Warrior, Inc. Address: P.O. Box 399 Phone: (785) 398-2270 Operator License #: 4058 Type of Well: Oil Docket #: The plugging proposal was approved on: 11/16/04 by: Mike Maier (KCC District Agent's Name) Is ACO-1 filed? [X] Yes [] No If not, is well log attached? [] Yes [X] No Producing Formation(s): List All (If needed attach another sheet) Mississippian Depth to Top: 4244' Bottom: 4250' T.D. 4250'

API Number: 15-135-22652-00-00 Lease Name: Foos Well Number: 1 Spot Location (QQQQ): NE-SW-SE- 990 Feet from [] North / [X] South Section Line 1650 Feet from [X] East / [] West Section Line Sec. 5 Twp. 19 S. R. 21 [] East [X] West County: Ness Date Well Completed: 9/5/84 Plugging Commenced: 11/16/04 Plugging Completed: 11/17/04

Show depth and thickness of all water, oil and gas formations.

Table with 7 columns: Formation, Content, From, To, Size, Put In, Pulled Out. Row 1: Mississippian, oil/water, 4445', 4250', 8 5/8", 369', None. Row 2: 5 1/2", 4245', None.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.


Mix 15 sacks of cement and pump down 8 5/8" Braden head and pressure to 350 psi and held, mix 25 sacks cement with 300# of hulls, mix 20 sacks of gel, mix 120 sacks of cement and pump down 5 1/2" casing, max pressure of 1000 psi, shut in with 500 psi. Return next day and top off casing with 20 sacks of cement. All cement was 60/40 POZ 6% gel. Job complete.

Name of Plugging Contractor: Swift Services, Inc. License #: 32382 Address: N. Highway 283, Ness City, KS 67560

Name of Party Responsible for Plugging Fees: American Warrior, Inc. State of Kansas County, Ness, ss.

RECEIVED NOV 19 2004 KCC WICHITA

Scott Corsair (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) [Signature] (Address) 210 Avenue A, Bazine, KS 67516

SUBSCRIBED and SWORN TO before me this 18th day of November, 20 04. Bernice Moore, Notary Public, My Commission Expires: 2/17/06

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

[Handwritten mark]