

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 30 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
September 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: L.D. Drilling, Inc.

Address: 7 SW 26th Ave. Gt. Bend, Kansas 67530

Phone: (620) 793-3051 Operator License #: 6039

Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: _____ (Date)

by: Virgil Clothier (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. 3286'

API Number: 15-053-20,881-00-00

Lease Name: Hickel

Well Number: 5

Spot Location (QQQQ): _____ - NW - SW - SE
990 Feet from North / South Section Line

2310 Feet from East / West Section Line

Sec. 30 Twp. 17 S. R. 10 East West

County: Ellsworth

Date Well Completed: 9/8/1984

Plugging Commenced: 10-25-04

Plugging Completed: 10-25-04

KCC
Ben
11/22/04
RBDms

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	302'	None
				5-1/2"	3279'	2004'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed, from _____ feet to _____ feet each set.

Plugged off bottom with sand to 3230' and 5 sacks cement. Cut casing loose @2004, pulled up to 1300', pumped 35 sacks cement, pulled up to 950', pumped 85 sacks cement, pulled up to 360' and circulated 200 sacks cement to surface. 60/40 pos, 4% gel. Plugging Complete.

Name of Plugging Contractor: Mike's Testing & Salvage, Inc. License #: 31529

Address: P.O. Box 467 Chase, Kansas 67524

Name of Party Responsible for Plugging Fees: L.D. Drilling, Inc.

State of Kansas County, Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) on above-described well, being first day


sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Mike Kelso

(Address) P.O. Box 467 Chase, Kansas 67524

SUBSCRIBED and SWORN TO before me this 16th day of November, 2004

Irene Herzberg My Commission Expires: _____
Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
NOV 19 2004
KCC WICHITA

Ben