

STATE OF KANSAS
 -STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

Well was Completed In

June 13, 1943

15-147-00581-00-28

API NUMBER

LEASE NAME Templeton

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER 2W

1650 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 14 TWP. 5 RGE. 20 (W)

COUNTY Phillips

Date Well Completed 6-13-43

Plugging Commenced 1-4-85

Plugging Completed 1-18-85

LEASE OPERATOR Cities Service Oil & Gas Corporation

ADDRESS 3545 N.W. 58th Street, Oklahoma City, OK 73112

PHONE# (405) 949-4400 OPERATORS LICENSE NO. 5447

Character of Well Input

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District 6

Is ACO-1 filed? No If not, is well log attached? No Well was drilled on 6-13-43

Injection Formation LKC Depth to Top 3230 Bottom 3460 T.D. 3630

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
LKC	- - -	3230	3460	8-5/8"	N/A	0
				5-1 1/2"	3630	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
 1-4-85: Ran AD-1 packer down tubing. Ran open end tubing to 2000'. Pumped 100 sx 50-50 Pozmix + 6% gel & 3% CC; Pulled tubing to 1000'; pumped 1 sx hulls, 100 sx cement; pulled out of hole. Swedged 5-1/2" csg. Pumped 45 sx cement. Tied into 8-5/8" - 5-1/2" annulus. Started pumped in developed several leaks at surface. Tied back onto 5 1/2"; pumped in 153 sx cement. SI at 500 psi (over)
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Services License No. _____

Address Box 47, Oberlin, KS 67749 STATE CORPORATION COMMISSION

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

Del Oliver
 (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Del Oliver
 (Address) 3545 N.W. 58th Street
Oklahoma City, Oklahoma 73112

SUBSCRIBED AND SWORN TO before me this 25 day of Feb., 19 85

My Commission Expires: 6-12-88 Joyce S. Doster Notary Public

Continued:

Total cement in 5½" csg: 4002sx 50-50 Pozmix. State witness: Dale Bathazor.
1-18-85: Mixed 16 sx common; poured down 8-5/8" - 5-1/2" annulus filled to surface.
P & A completed.