

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas. 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

20,175-0070
API NUMBER 15.147-8017 01
LEASE NAME BOGART A #1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER A #1
Approx. 2260 Ft. from S Section Line
Approx. 1000 Ft. from E Section Line

LEASE OPERATOR Rains & Williamson Oil Co., Inc.

ADDRESS 935 Page Court--220 West Douglas Wichita, Ks.

PHONE# 316 265-9686 OPERATORS LICENSE NO. 5146

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Hays

Which KCC/KDHE Joint Office did you notify? Hays

Is ACO-1 filed? _____ If not, is well log attached? Yes

Producing Formation Lan.- KC Depth to Top 3102 Bottom 3349 T.D. 3369

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	<u>3179-3183</u> <u>3160-64</u>			<u>4 1/2</u>	<u>3368</u>	<u>None</u>
<u>Lan.-kc</u>	<u>3201-3205</u>	<u>3210-</u>	<u>3210-14</u>			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Halliburton Service, down 4 1/2 casing with 50 saxes cement, 50-50 poz mix, 75 saxes cement with 2 saxes hulls. Released plug followed with 75 saxes cement, closed in at 300 lbs., thru perfs 1385-1390. Down 8 5/5 with 175 saxes cement with 2 saxes Flocele and 2 saxes hulls, closed in at 250 lbs., down 4 1/2 with 25 saxes cement, closed in at 200 lbs., plugged down at 11:30 a.m.
(If additional description is necessary, use BACK of this form.) 5-24-85

Name of Plugging Contractor Rains & Williamson Oil Co., Inc. License No. 682

Address P. O. Box 166

STATE OF Kansas COUNTY OF Ellis, ss.

Rains & Williamson Oil Co., Inc.

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Paul Stephens
Paul Stephens, Supt.

(Address) Box 166, Pratt, Kansas 67124

SUBSCRIBED AND SWORN TO before me this 8th day of August, 19 85

Mary Alice Rupp
NOTARY PUBLIC
State of Kansas
MY APPT. EXPIRES 2-29-88

My Commission Expires: 2-29-88

RECEIVED
STATE CORPORATION COMMISSION

AUG 15 1985

Form CP-4
Revised 08-84